

4701 New Jersey Avenue  
Wildwood, NJ 08260  
Phone: 609-854-3311  
Fax: 609-854-4323  
www.deblasioassoc.com

**DEBLASIO &  
ASSOCIATES**  
CONSULTING ENGINEERS AND PLANNERS

# FAX

## Cover Letter

TO:	All Bidders	FROM:	Marc DeBlasio, P.E., P.P., C.M.E.
FAX:		PAGES:	2
PHONE:		DATE:	June 30, 2021
RE:	Borough of Stone Harbor Beach Patrol Headquarters SH-C-020	CC:	Suzanne Stanford, Clerk (via email) Robert Smith, Administrator (via email) William McLees (via email) Jeff Moore, PE (via email)

Urgent     For Review     Please Comment     Please Reply     Please Recycle

Comments: Please find enclosed Addendum No. 2. This addendum must be returned with all bids. The failure to return the signed receipt with the contract forms will result in a non-responsive bid.

**ADDENDUM NO. 2**

**To All Bidders of Beach Patrol Headquarters  
Borough of Stone Harbor  
Cape May County, New Jersey  
D&A Project #: SH-C-020**

You are hereby notified in accordance with bid documents of the above captioned project that the following has been issued to clarify the meaning of the plans and specifications and that the conditions and specifications set forth in said addenda are to be original contract documents.

**In accordance with ITB-3, a written request must be received at least seven (7) business days prior to the date fixed for the opening of the bid for goods and services. Therefore, no further questions will be accepted after Thursday, July 1, 2021.**

**QUESTIONS**

- Q.** Drawing A2.00 Elevation Key Notes BB10 is not identified please clarify. Keynote SS10 indicates smooth shiplap siding but elevation drawings indicate it to be a type of hard shingle siding. Please clarify will all siding be factory painted or painted in the field.
- A.** **BB10 is intended to be a 3/8" thick 48"X96" sheet PVC finish with 4/4x4 PVC trim battens. SS10 is a fibercement shiplap finish, there is no shingle finish for siding. All fibercement products should be provided with a factory painted finish.**
  
- Q.** Drawing A1.03 indicates Hardie Trim at windows, drawing A5.00 indicates Fypon at window head detail. If Hardie Trim is required for all windows, building corner, and overhead door trim, please clarify size and thickness of Hardie Trim at each location.
- A.** **A 4/4X4 Hardie Trim fibercement casing is required at all windows and doors. Fypon 6" classic crossheads are to be provided. Additionally 4/4X4 Hardie Trim shall be provided at corners and 4/4X6 Hardie Trim shall be provided at overhead door trim.**

**THIS ADDENDUM MUST BE RETURNED WITH ALL BIDS. THE FAILURE TO RETURN THIS SIGNED RECEIPT WITH THE CONTRACT FORMS WILL RESULT IN A NON-RESPONSIVE BID**

I acknowledge receipt of this addendum.

\_\_\_\_\_  
Signature

\_\_\_\_\_  
Company