# VINELAND SENIOR CENTER

103 SOUTH 6TH STREET, BLOCK 4007 LOT 1, VINELAND, NEW JERSEY 08360 EXTERIOR RENOVATION IMPROVEMENTS










#### PROJECT TEAM CODE REFERENCES GENERAL NOTES PROJECT INFORMATION 1. INTERNATIONAL BUILDING CODE, NEW JERSEY EDITION, 2021 (IBC) THE CONTRACTOR SHALL CHECK AND VERIFY ALL DIMENSIONS AND FIELD CONDITIONS PRIOR TO STARTING CONSTRUCTION AND SHALL BRING TO THE ATTENTION OF THE ARCHITECT ANY DISCREPANCIES **PROJECT:** VINELAND SENIOR CENTER (PATRICK FIORILLI SENIOR CENTER) WHICH ALTER OR IMPEDE THE ORIGINAL OR INTENDED DESIGN. GENERAL CONTRACTOR IS RESPONSIBLE FOR THE COORDINATION OF ALL WORK AND OF ALL TRADES. THE CITY OF VINELAND, NEW JERSEY 2. UNIFORM CONSTRUCTION CODE, STATE OF NEW JERSEY (NJAC) 640 EAST WOOD STREET, 2. ARCHITECT IS NOT RESPONSIBLE FOR EXISTING CONDITIONS. LOCATION: 103 SOUTH 6TH STREET VINELAND, NEW JERSEY 08360 3. NATIONAL STANDARD PLUMBING CODE, 2021 (NSPC) VINELAND, NEW JERSEY Ø836Ø 3. ALL WORK MUST COMPLY WITH THE LATEST VERSION OF THE STATE OF NEW JERSEY UNIFORM CONSTRUCTION CODE AND ALL SUBCODES. PHONE: 856-194-4000 4. NATIONAL ELECTRIC CODE, 2020 (NFPA 10) OCCUPANCY GROUP: A-3, ASSEMBLY 4. CONTRACTORS MUST COMPLY WITH ALL STATE AND FEDERAL OSHA SAFETY REGULATIONS. CONSTRUCTION MANAGER: 5. INTERNATIONAL MECHANICAL CODE, 2021 RENOVATION/NEW: EXTERIOR IMPROVEMENTS, RENOVATIONS NEW ROAD CONSTRUCTION MANAGEMENT 5. DO NOT "SCALE" FROM THESE DRAWINGS. THE DIMENSIONS INDICATED ON THE DRAWINGS SHALL GOVERN. IF A DISCREPANCY IS NOTED, IMMEDIATELY NOTIFY THE ARCHITECT. 6. INTERNATIONAL FUEL GAS CODE, 2021 1816 GREENTREE ROAD, 6. ALL DIMENSIONS INDICATED ON DRAWINGS ARE MEASURED TO THE FACE OF STUD FRAMING, EDGES OF CONCRETE SLABS, FACE OF MASONRY, OR FACE OF CONCRETE WALL. (UNLESS NOTED OTHERWISE) THE NUMBER OF STORIES: CHERRY HILL, NEW JERSEY 08003 7. ENERGY SUBCODE, AMERICAN SOCIETY OF HEATING, REFRIGERATION, AND DIMENSIONS INDICATED ARE NOT CLEAR FINISH TO FINISH DIMENSIONS. AIR-CONDITIONING ENGINEERS, ASHREA 90:1-2019 PHONE: 856-424-8888 856-424-1688 1. MASONRY DIMENSIONS INDICATED ON DRAWINGS ARE "NOMINAL" DIMENSIONS (NOT ACTUAL). CONCRETE DIMENSIONS INDICATED ON DRAWINGS ARE ACTUAL DIMENSIONS. 8. ICC/ANSI AIIT.I-2017, AMERICAN NATIONAL STANDARD, ACCESSIBLE AND USABLE BUILDINGS AND FACILITIES (ICC/ANSI) 8. LIFE SAFETY SYSTEMS SHALL REMAIN OPERABLE DURING CONSTRUCTION. BRUCE FARRELL EMAIL: bfarrell@newroadconstruction.com 9. CONTRACTOR SHALL SUBMIT SHOP DRAWINGS AND SAMPLES FOR ARCHITECT AND OWNER'S REVIEW PRIOR TO PURCHASING OR FABRICATION OF PROPOSED ITEMS. ARCHITECT: 10. CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL PERMITS FOR THIS PROJECT AND PAYMENT OF SAME. OSK DESIGN PARTNERS, PA II. WORK REQUIRING EXCESSIVE AND/OR DISTURBING NOISE TO NORMAL OPERATION OF THE BUILDING SHALL BE REVIEWED WITH THE OWNER PRIOR TO THE 475 WHITE HORSE PIKE, START OF SUCH WORK. THE OWNER RESERVES THE RIGHT TO RESTRICT ANY WORK THEY DEEM DISTURBING TO THE OPERATION OF THE BUILDING. ALL SUCH COLLINGSWOOD, NEW JERSEY Ø81Ø7 WORK SHALL BE COORDINATED WITH THE OWNER PHONE: 856-854-0580 FAX: 856-854-0993 PRIOR TO FINAL BID AND OR THE START OF CONSTRUCTION THE CONTRACTOR SHALL VERIFY EXISTING CONDITIONS AND IDENTIFY IN WRITING TO THE ARCHITECT ANY DISCREPANCIES OF CONFLICTS BETWEEN THE EXISTING AS-BUILT CONDITIONS AND THOSE SHOWN ON THE CONSTRUCTION DOCUMENTS CONTAINED HEREIN. COMMENCEMENT OF WORK INDICATES THE CONTRACTOR'S ACCEPTANCE OF THE EXISTING JERRY BLACKMAN, AIA CONDITIONS AND THE ASSUMPTION OF RESPONSIBILITY, INCLUDING ALL COSTS AND EXPENSES, FOR PROVIDING A FINISHED PRODUCT AS EMAIL: jblackman@oskdp.com DESIGNED AND PERMITTED. 01-08-2025 ISSUED FOR BIDDING BRAD WAMPLER, AIA 13. ITEMS THAT ARE NOT PART OF THE CONTRACTOR'S CONTRACT ARE INDICATED BY "(NIC)" AND ARE SHOWN DASHED. DRAWING ISSUE EMAIL: bwampier@oskdp.com DATE



RESERVED			
RIGHTS			
ALL RI			
	NO.	DESCRIPTION	DATE
NERS, P.A.		REVISION SCHEDU	JLE
IZ"			

IGN P	DRAWN BY:	DC/BJW
DES	CHECKED BY:	JSB
OSK	DATE:	<i>0</i> 1- <i>0</i> 8-2 <i>0</i> 25
П	SCALE:	NO SCALE
		·

2199.01

## VINELAND SENIOR CENTER

103 SOUTH 6TH STREET, BLOCK 4007 LOT 1, VINELAND, NEW JERSEY 08360 INTERIOR ALTERATIONS / RENOVATIONS

#### PROJECT INFORMATION PLAN REVIEW RECORD **PROJECT:** VINELAND SENIOR CENTER HEIGHT AND AREA COMPUTATIONS: LOCATION: 103 S 6TH STREET VINELAND, NEW JERSEY 08360 A. OCCUPANCY GROUP CLASSIFICATION (SECTION 302.1) : (A-3) ASSEMBLY B. ACTUAL BUILDING AREA AND HEIGHT: OCCUPANCY GROUP: A-3, ASSEMBLY RENOVATION/NEW: BUILDING ALTERATION BASEMENT FLOOR: : 2,981 SF 2,953 SF NUMBER OF STORIES: ONE-STORY WITH BASEMENT TOTAL FLOOR AREA: : 5,934 SF 2. HEIGHT TOTAL HEIGHT : 1-STORIES, 30.25' (EXCLUDING CUPOLA) C. TYPE OF CONSTRUCTION: : '3B' UNPROTECTED : 40-FEET 1. ALLOWABLE BUILDING HEIGHT (TABLE 504.3) PROJECT TEAM 2. ALLOWABLE NUMBER OF STORIES (TABLE 504.4) : 1-STORIES 3. ALLOWABLE BUILDING AREA, At (TABLE 5062) : 6,000 SF THE CITY OF VINELAND, NEW JERSEY 640 EAST WOOD STREET, TYPE OF CONSTRUCTION (CHAPTER 6) AND FIRE-RESISTIVE CONSTRUCTION (CHAPTER 1) VINELAND, NEW JERSEY 08360 PHONE: 856-794-4000 A. FIRE RESISTANCE RATING REQUIREMENTS FOR BUILDING ELEMENTS (TABLE 601) - 3B CONSTRUCTION CONSTRUCTION MANAGER: 1. STRUCTURAL FRAME : Ø HOUR 2. BEARING WALLS NEW ROAD CONSTRUCTION MANAGEMENT EXTERIOR : Ø HOURS 1816 GREENTREE ROAD. INTERIOR : Ø HOURS CHERRY HILL, NEW JERSEY 08003 3. NONBEARING WALLS AND PARTITIONS EXTERIOR : SEE TABLE 602 PHONE: 856-424-8888 : Ø HOURS 856-424-1688 4. FLOOR CONSTRUCTION : Ø HOURS : Ø HOURS 5. ROOF CONSTRUCTION BRUCE FARRELL EMAIL: bfarrell@newroadconstruction.com B. FIRE RESISTANCE RATING REQUIREMENTS FOR EXTERIOR ARCHITECT: WALLS BASED ON FIRE SEPARATION DISTANCE (TABLE 105.5) OSK DESIGN PARTNERS, PA FIRE SEPARATION DISTANCE TYPE OF CONSTRUCTION FIRE-RESISTANCE RATING 475 WHITE HORSE PIKE, COLLINGSWOOD, NEW JERSEY 08107 PHONE: 856-854-0580 FAX: 856-854-0993 EAST: 5 FT+ 1 HOURS JERRY BLACKMAN, AIA SOUTH: 30 FT+ EMAIL: jblackman@oskdp.com WEST: 30 FT+ Ø HOURS BRAD WAMPLER, AIA EMAIL: bwampler@oskdp.com C. MAXIMUM AREA OF EXTERIOR WALL OPENINGS (TABLE 105.8) CODE REFERENCES SOUTH EAST WEST CLASSIFICATION OF OPENING 3Ø FT+ 5 FT+ 3Ø FT+ 3Ø FT+ I. INTERNATIONAL BUILDING CODE, NEW JERSEY EDITION, 2021 (IBC) NO LIMIT UNPROTECTED, NON-SPRINKLERED NO LIMIT NO LIMIT 10% 2. UNIFORM CONSTRUCTION CODE, STATE OF NEW JERSEY (NJAC) D. FIRE RESISTANCE RATING REQUIREMENTS FOR MISCELLANEOUS BUILDING ELEMENTS 3. NATIONAL STANDARD PLUMBING CODE, 2021 (NSPC) FIRE WALLS (TABLE 706.4) : NOT APPLICABLE 4. NATIONAL ELECTRIC CODE, 2020 (NFPA 10) FIRE DOOR & FIRE SHUTTER (TABLE 115.4) : NOT APPLICABLE 5. INTERNATIONAL MECHANICAL CODE, 2021 FIRE BARRIERS (SECTION 101.1) : I HOUR EXIT ENCLOSURES (SECTION 713.4, 1023, \$ 1024) 6. INTERNATIONAL FUEL GAS CODE, 2021 : I HOUR EXIT ENCLOSURE DOORS (TABLE 115.4) SHAFTS AND ELEVATOR HOISTWAYS (SECTION 708) : 2 HOUR T. ENERGY SUBCODE, AMERICAN SOCIETY OF HEATING, REFRIGERATION, AND MIXED OCCUPANCY (TABLE 508.4) : NOT APPLICABLE AIR-CONDITIONING ENGINEERS, ASHREA 90.1-2019 FIRE PARTITIONS (SECTION 109) : NOT APPLICABLE CORRIDOR WALLS (TABLE 1018.1) DRAWING LIST CORRIDOR DOORS (TABLE 115.4) : NOT APPLICABLE : I HOUR SMOKE BARRIERS (SECTION 110.3) ARCHITECTURAL DRAWING LIST: STRUCTURAL FRAME (SECTION 104) : Ø HOURS COVER SHEET - PROJECT INFORMATION & GENERAL NOTES CS-Ø FLOOR CONSTRUCTION (SECTION 111.3) : Ø HOURS CS-1 COVER SHEET - PROJECT INFORMATION & PLAN REVIEW RECORD CS-2 COVER SHEET - ACCESSIBILITY PLAN REVIEW RECORD & PLAN SYMBOLS ROOF CONSTRUCTION (SECTION 111.3) : O HOURS COVER SHEET - ALTERATIONS SUB-CODE REVIEW SUMMARY CS-3 E. FIRE BLOCKING (SECTION 717.2) D1-1 BASEMENT DEMOLITION PLAN -INSTALLED IN LOCATIONS SPECIFIED IN SECTIONS 117.2.2 THROUGH 117.2.7 D1-2 FIRST FLOOR DEMOLITION PLAN SP-1 SITE WALL REPAIR PLAN F. DRAFTSTOPPING (SECTION 117.4) -INSTALLED AS INDICATED ON PLANS TO SUBDIVIDE CONCEALED ROOF SPACES INTO MAX HORIZONTAL AREAS OF 3,000 SF. BASEMENT FLOOR PLAN FIRST FLOOR PLAN BASEMENT FLOOR REFLECTED CEILING PLAN FIRST FLOOR REFLECTED CEILING PLAN FLOOR PLANS & NOTES BUILDING ELEVATIONS BUILDING ELEVATIONS BUILDING ELEVATIONS A2-3 BUILDING ELEVATIONS A2-5 FRONT ELEVATIONS & NOTES LEFT SIDE ELEVATION & NOTES REAR ELEVATION & NOTES A2-8 RIGHT SIDE ELEVATIONS & NOTES STAIR ENCLOSURE SECTIONS AND DETAILS A5-1 SCHEDULES A5-2 WINDOW DETAILS WINDOW DETAILS TRIM DETAILS / INTERIOR ELEVATION REPAIR A5-4 MILLWORK PLANS AND ELEVATIONS MILLWORK DETAILS

#### INTERIOR FINISHES (CHAPTER 8)

A. INTERIOR WALL & CEILING FINISH REQUIREMENTS BY OCCUPANCY (TABLE 803.11 SPRINKLERED)

	(A-3) ASSEMBLY
INTERIOR EXIT STAIRWAYS, RAMPS & PASSAGWAYS CORRIDORS & ENCLOSURE FOR EXIT ACCESS STAIRS & RAMPS ROOMS AND ENCLOSED SPACES	CLASS A CLASS A CLASS C

- B. INTERIOR FLOOR FINISH
  - 1. TESTING REQUIREMENTS (SECTION 804.4.1): SHALL COMPLY WITH DOC FF-1 'PILL TEST' OR ASTM D2859
- 2. MINIMUM CRITICAL RADIANT FLUX (SECTION 804.4.2): NOT LESS THAN CLASS II MATERIALS.
- C. DECORATIVE MATERIALS AND TRIM (SECTION 806.1.2 \$ 806.5)
  - NONCOMBUSTIBLE MATERIALS (SECTION 806.2): THE PERMISSIBLE AMOUNT OF NONCOMBUSTIBLE MATERIALS SHALL NOT BE PROHIBITED.
- 2. INTERIOR TRIM (SECTION 806.7): MATERIALS (OTHER THAN FOAM PLASTIC) SHALL HAVE A MINIMUM CLASS C FLAME SPREAD AND SMOKE-DEVELOPED INDEX, WHEN TESTED IN ACCORDANCE WITH ASTM ES4 OR UL 123. COMBUSTIBLE TRIM, EXCLUDING HANDRAILS AND GUARDRAILS, SHALL NOT EXCEED 10-PERCENT OF THE SPECIFIC WALL OR CEILING AREA IN WHICH IT IS ATTACHED.

NOT REQUIRED

3. INTERIOR FLOOR-WALL BASE (SECTION 806.8): FLOOR-WALL BASE LESS THAN 6-INCHES IN HEIGHT SHALL NOT BE LESS THAN CLASS II MATERIALS IN ACCORDANCE WITH NFPA 253. (EXCEPTION: INTERIOR TRIM MATERIALS COMPLYING WITH SECTION 806.7)

FIRE PROTECTION SYSTEMS (CHAPTER 9)	
AUTOMATIC SPRINKLER SYSTEMS (SECTIONS 9032.13)	

1. OCCUPANCY GROUP: A-3, 3B CONSTRUCTION STANDPIPE SYSTEMS (SECTION 905.3) 1. OCCUPANCY GROUP: A-3 FIRE DEPARTMENT CONNECTIONS (SECTION 912) 1. OCCUPANCY GROUP: A-3 FIRE ALARM & DETECTION SYSTEMS (SECTIONS 907.2.2)

FIRE EXTINGUISHERS (SECTION 906.1): -SEE FLOOR PLANS FOR LOCATIONS. EXTINGUISHERS TO COMPLY WITH NFPA-10.

ROOF COVERING (SECTION 1505.1) -CLASS 'C' MINIMUM. (CLASS "A" MATERIALS ACTUALLY USED)

#### MEANS OF EGRESS (CHAPTER 10)

1. OCCUPANCY GROUP: A-3

A. OCCUPANCY LOAD (SECTION 1004 & TABLE 1004.1.2)

USE GROUP: A-3			
<u>LOCATION</u>	NET FLOOR AREA	SQ. FT/ PERSON	<u>TOTAL</u>
BASEMENT FLOOR	2,981 SF	35 NET	85 PERSONS
FIRST FLOOR	2,953 SF	35 NET	85 PERSONS
		TOTAL OCCUPANCY:	170 PERSONS

B. CAPACITY OF EXITS (SECTION 1005.1) CAPACITY UNIT EGRESS WIDTH/ OCCUPANT LOAD

USE GROUP: A-3 STAIRWAYS: 0.3" PER OCCUPANT DOOR, RAMPS CORRIDOR: 0.2" LOCATION STAIRWAYS DOORS, RAMPS, CORRIDORS BASEMENT FLOOR 36" MIN. DOORS, 44" MIN. CORRIDORS FIRST FLOOR 36" MIN. DOORS, 44" MIN. CORRIDORS

C. NUMBER OF EXITS (SECTION 1021, TABLE 1021.1)

USE GROUP: A-3 <u>LOCATION</u> OCCUPANT LOAD REQUIRED PROPOSED 1-500 PERSONS 2 EXITS BASEMENT FLOOR 2 EXITS 1-500 PERSONS 2 EXITS FIRST FLOOR

- D. EXIT SIGNS COMPLYING WITH SECTION 1013 ARE REQUIRED THROUGHOUT THE BUILDING ADDITION AT ALL EXITS, EXIT ACCESS DOORS, AND ALONG THE PATH OF EGRESS TRAVEL TO EXITS.
- G. EXIST ACCESS: COMMON PATH OF EGRESS TRAVEL (TABLE 1006.2.1): OCCUPANCY GROUP: A-3 = 15 FT MAX.
- H. EXIT ACCESS TRAVEL DISTANCE (SECTION 1017 & TABLE 1017.2): OCCUPANCY GROUP: A-3 = 200 FT MAX.
- CORRIDORS (SECTION 1020)
- 1. CONSTRUCTION (SECTION 1018.1) CORRIDORS SHOULD BE FIRE-RESISTANCE RATED IN ACCORDANCE WITH TABLE 1020.1

OCCUPANCY GROUP OCCUPANT LOAD SERVED BY CORRIDOR REQUIRED FIRE-RESISTANCE RATING GREATER THAN 30

- 2. CORRIDOR WIDTH & CAPACITY (SECTION 10202 & TABLE 10202)
- CORRIDOR WIDTH SHALL BE AS DETERMINED IN SECTION 1005.1, BUT NOT LESS THAN 44".
- 3. DEAD ENDS (SECTION 1020.4) EXIT ACCESS SHALL BE ARRANGED SUCH THAT THERE ARE NO DEAD END CORRIDORS MORE THAN 20 FEET IN LENGTH.

### PLAN REVIEW & GENERAL NOTES

- BUILDING HEIGHT AND ALLOWABLE STORIES ABOVE GRADE PLANE HAVE BEEN DETERMINED FROM TABLES 504.3 AND 504.4 FOR NON-SPRINKLERED BUILDINGS. THE BUILDING AREA (A,) HAS BEEN DETERMINED FROM TABLE 5062 USING THE ALLOWABLE AREA FACTOR 'NS' FOR BUILDINGS OF TWO OR MORE STORE ABOVE THE GRADE PLANE.
- THE BUILDING IS ELIGIBLE FOR A FRONTAGE INCREASE ACCORDING TO SECTION 5063, 15% OF
- 4. IN GENERAL, DOORS MUST BE AT LEAST 36" WIDE (TO ACHIEVE MINIMUM CLEAR WIDTH OF 32" REQUIRED BY SECTION 1008.1.1). CORRIDORS MUST BE AT LEAST 44' WIDE ACCORDING TO SECTION 10182. STAIRS MUST BE AT LEAST 44" WIDE ACCORDING TO SECTION 1009.1 WITH
- THE CONTRACTOR SHALL CHECK AND VERIFY ALL DIMENSIONS AND FIELD CONDITIONS PRIOR TO STARTING CONSTRUCTION
- 6. DO NOT "SCALE" FROM THESE DRAWINGS. THE DIMENSIONS INDICATED ON THE DRAWINGS
- EDGES OF CONCRETE SLABS, FACE OF MASONRY, OR FACE OF CONCRETE WALL. (UNLESS NOTED OTHERWISE) THE DIMENSIONS INDICATED ARE NOT CLEAR FINISH TO FINISH DIMENSIONS.
- 9. ITEMS THAT ARE NOT PART OF THE CONTRACTOR'S CONTRACT ARE INDICATED BY "(NIC)" AND ARE SHOWN DASHED.
- 10. MASONRY DIMENSIONS INDICATED ON DRAWINGS ARE "NOMINAL" DIMENSIONS (NOT ACTUAL).



THE BUILDING IS NOT EQUIPPED WITH AN AUTOMATIC FIRE SPRINKLER SYSTEM. THE ALLOWABLE

- THE BUILDING'S PERIMETER IS ON AN OPEN SPACE WITH A WIDTH GREATER THEN 30 FT.
- 3. A FIRE ALARM SYSTEM WILL BE NOT PROVIDED FOR THE BUILDING.
- HANDRAIL PROJECTIONS OF 41/5" MAX EACH.
- SHALL GOVERN. IF A DISCREPANCY IS NOTED, IMMEDIATELY NOTIFY THE ARCHITECT.
- ALL DIMENSIONS INDICATED ON DRAWINGS ARE MEASURED TO THE FACE OF STUD FRAMING.
- THE CABINETRY, CASEWORK, MILLWORK INDICATED ON THE DRAWINGS (WITH PLUMBING FIXTURES AND/OR APPLIANCES) IS PART OF THE CONTRACTOR'S CONTRACT. COORDINATE INSTALLATION OF ALL MILLWORK, CABINETRY AND CASEWORK WITH THE ARCHITECT (OWNER'S REPRESENTATIVE) TO VERIFY CONFIGURATIONS.
- CONCRETE DIMENSIONS INDICATED ON DRAWINGS ARE ACTUAL DIMENSIONS.



S

0

a

ERVE			
RESI			
GHTS			
ALL RIGHTS RESERVED			
	NO.	DESCRIPTION	DATE
RS, P.A.		REVISION SCHEDU	ILE

DRAWN BY:	DC
CHECKED BY:	JSB
DATE:	Ø3-14-2Ø25
SCALE:	AS NOTED

JOB NO.

Ø4-1Ø-25

01-08-25

DATE

<u>No.</u>

ISSUED FOR BUILDING PERMITS

DRAWING ISSUE

ISSUED FOR BIDDING

2199.01


# VINELAND SENIOR CENTER

103 SOUTH 6TH STREET, BLOCK 4007 LOT 1, VINELAND, NEW JERSEY 08360 BUILDING ALTERATION

CCESSIBLE SITE & EXT	TERIOR FA	CILITY RE	QUIREMENTS	BARRIER FR	EE ACCESS	SIBILITY REQU	IREMENTS	KE	Y TO SYMBOLS	/ HATCH	
PARKING: (SEE SITE PLAN)	CODE SECTION	REQUIREMENT	PROPOSED	ACCESSIBLE BUILDING REQUIREMENTS	CODE SECTION	REQUIREMENT	PROPOSED	EARTH	COMPACTED CRUSHED STONE	<u></u>	
TOTAL NUMBER OF ON-SITE PARKING SPACES	;	;	: (17) SPACES	RAMPS:				EARTHWORKS			
ACCESSIBLE PARKING SPACES REQUIRED	: IBC NJ 2018, 1106.1	: (1) SPACES	: (1) SPACES	SLOPE	: ICC/ANSI 4Ø5.2	: 1:12 MAX.	: NOT APPLICABLE	CAST-IN-PLAC	CE		
SIZE OF PARKING SPACE	: ICC/ANSI 5022	: 8' x 18' WITH	: 8' x 18' W/	MAX RISE PER RAMP RUN	: ICC/ANSI 405.6	: 30" MAX.	: NOT APPLICABLE	CONCRETE			
OIZE OF A MINING OF A OE	. 100/74101 3022	5' WIDE AIGLE	5'-0' WIDE AISLE	WIDTH	: ICC/ANSI 4Ø5.5	: 36' MIN.	: NOT APPLICABLE	FINISH WOOD	PLYWOOD	ROUGH	
SIGNAGE TYPE AT EACH ACCESSIBLE PARKING SPACE	: IBC NJ 2018, 1106.8	: RT-8 WITH	: RT-8 WITH RT-8P AND RT-8V	TOTAL LENGTH	:	;	: NOT APPLICABLE		PLYWOOD	ROUGH	
	IDC VI 1000 IIO/ F	RT-8P BELOW	BELOW	LANDING	: ICC/ANSI 4Ø5.7	: RAMP WIDTH x 5'-0" LONG AT	: NOT APPLICABLE	WOOD			
VAN ACCESSIBLE PARKING SPACES	: IBC NJ 2018, 1106.5	: (1) PER (6) SPACES	: (1) SPACES			EVERY 30'-0" MAX. RUN		MISCELLANEOUS	PAVERS		
AISLE WIDTH AT VAN SPACES	: ICC/ANSI 502.3.1	: 8'- <b>0'</b>	: 8'-0' WIDE	HANDRAILS	: ICC/ANSI 405.8	: DIA.   1/4"-2" O.D. HT. 2'-10"- 3'-2" TOP AND BOTTOM 12"	: NOT APPLICABLE	CONCRETE BL	DECORATIVE LOCK CONCRETE BLOCK		
VERTICAL CLEARANCE AT VAN SPACE	: ICC/ANSI 502.5	: 8'-2" MIN.	: UNLIMITED	DOORS:		EXTENSIONS					
BUILDING ENTRANCES				MIN. SIZE	: ICC/ANSI 40423	: 3'-0" x 6'-8"	: 3'-0" × 7'-0" MIN. FOR	MASONRY BRICK	BRICK (ELEVATIO	<u>N)</u>	
TOTAL NUMBER OF ENTRANCES	;	;	: (3) ENTRANCES	TINC OILL	. 100/ANOT 4042.5	. 5 - 6 10 - 6	ACCESSIBLE DOORS	STEEL			
TOTAL NUMBER OF PUBLIC ENTRANCES	:	:	: (1) ENTRANCES	THRESHOLD HEIGHT	: ICC/ANSI 4Ø42.5	: 1/2" MAX.	: 1/2" MAX.	METAL STEEL			
NUMBER OF ACCESSIBLE ENTRANCES	: IBC NJ 2018, 1105.1	: (1) ENTRANCE	: (2) ENTRANCES	HARDWARE	: ICC/ANSI 4042.7	: LEVER, PUSH/ PULLS, PANIC	: LEVER, PUSH, PULL, PANIC	[000000000]	FILL RIGID		
CHANGE IN GRADE ( EXTERIOR TO INTERIOR )	: ICC/ANSI 303.2	: 1/2" MAX.	: 1/2" MAX.					INSULATION	FILL RIGID		
				ACCESSIBLE ROUTES:				GYPSUM WALL	BOARD	<u> </u>	
NIMUM NUMBER OF	REQUIRED	PLUMBING	G FIXTURES	MIN. WIDTH	: ICC/ANSI 403.5	: 36'	: 36' MIN.	FINISHES		<del></del>	
JSE GROUP: A-3	~			MIN. DOORWAY WIDTH (OPENINGS WITHOUT DOORS)	: ICC/ANSI 403.5	: 32" NOT TO EXCEED 24" DEPTH	: 36' MIN.		NEW DOOR AND FRAME	CHASE OR OPENING	
JOE GROUP: A-3  A. FLOOR AREA:				MIN. VERTICAL CLEARANCES	: ICC/ANSI 307.4	: 6'-8"	: 7'-Ø" MIN.			ACCESSIBILITY CLEARANCES	
BASEMENT FLOOR: 2,981 SF FIRST FLOOR: 2,953 SF				TOILET FACILITIES:	CODE SECTION	REQUIREMENT	PROPOSED				
TOTAL FLOOR AREA: 5,934 SF				SEAT HEIGHT	: ICC/ANSI 604.4	: 15'-19'	: 15'-19'		(1 HR.) FIRE RATED PARTITION	A.P. ACCESS PANEL	
B. OCCUPANCY PER EGRESS REQUIREMENTS: (170) PERS (GROUP A-3 AREA/ 35 SF/PERSON FOR DAY CARE)	BONS FOR BUILDING.			CONTROLS HEIGHT	: ICC/ANSI 604.6	: 44" MAX.	: 44' MAX.		THE RAILD PARTITION	B. CONCRETE FILLED, GALVANIZED STI PIPE BOLLARD WITH PEWTER FINISH	EL
C. OCCUPANCY FOR PLUMBING FIXTURE REQUIREMENTS:									(2 HR.) FIRE RATED PARTITION	RD 4' DIA. ROOF DRAIN. W/ 4' DIA. DOU	NSPOUT.
OCCUPANCY = EGRESS OCCUPANCY (*B ABOVE) X 3  D. NUMBER OF PERSONS FOR EACH SEX: (51) PERSONS	3			GRAB BARS	: ICC/ANSI 604.5	: 1 1/4" - 1 1/2" O.D.	: 1 1/2" O.D.		(1 HR.) FIRE RATED BARRIER	SEE ROOF PLAN.	
EACH SEX = NSPC OCCUPANCY (*C ABOVE) x 50%				DIAMETER	:	: 33' - 36'	: 33'			SECONDARY ROOF DRAIN. TO GRAD BE 4' ABV. ROOF SURFACE. SEE RO	PE. TOP TO POF PLAN.
E. TOTAL FIXTURES REQUIRED:  1. WATER CLOSETS				HEIGHT	:	: 3'-0", 3'-6", 1'-6"	: 3'-0", 3'-6", 1'-6"		(2 HR.) FIRE RATED BARRIER	$\Box$ D6 4" D1A. ROUND DOWNSPOUT FROM G1	ITTER
MALE-2 FEMALE-2  2. LAVATORIES  MALE-2 FEMALE-2				LENGTH	:	: 15"-48" TO CENTER LINE	: 24" TO CENTER LINE MAX.	^		<b>♠</b> 1	
MALE- 2 FEMALE- 2  F. MALE FIXTURES PROVIDED:				TOILET PAPER HOLDER HEIGHT	: ICC/ANSI 604.7		: SEE DRAWING A5-1	<u></u>	REVISION NUMBER	BUILDING OR WALL S	ECTION .
<ol> <li>WATER CLOSETS = 1</li> <li>URINALS = 2</li> </ol>				CLEAR FLOOR AREA	: ICC/ANSI 604.3 OR ICC/ANSI 604.8	: 56" MIN. x 60" MIN. 59" MIN. x 60" MIN.		$\langle W1 \rangle \langle S1 \rangle$	WINDOW TYPE/ALUM. STOREFRONT TYPE	DETAIL	
LAVATORIES= 2				NUMBER OF WATER CLOSETS	: NSPC TABLE 7.21.1	: 2 MALE, 2 FEMALE	: (2) MALE, (2) FEMALE	(101)	DOOR AND FRAME NUMBER	` <b></b>	
G. FEMALE FIXTURES PROVIDED:  1. WATER CLOSETS = 2  2. LAVATORIES = 2				NUMBER OF ACCESSIBLE WATER CLOSETS	: IBC NJ 2015, 1109.2.2	: (1) PER TOILET FACILITY	: (2) MALE, (2) FEMALE	1)——	PARTITION TYPE	ELEVATION DETAIL	
H. DRINKING FOUNTAINS: 1 PER 100 OCCUPANTS. NSPC 5	SECTION 1215 INDICATES A KITC	CHEN, OR BAR SINK MAY MEET TI	4E		•	(4) TOTAL	(3) TOTAL	(A)	TOILET ROOM ACCESSORY	ELEVATION, DATUM C	R BENCHMAR
REQUIREMENT FOR DRINKING WATER FACILITIES FOR E				NUMBER OF URINALS	: NSPC TABLE 7.21.5, a.	: 50% OF REQ'D W.C. MAX.	: (Ø) PROVIDED			Hoft pipp thoft phoet	
I. (1) SERVICE SINK IS REQUIRED PER FLOOR. (1) SERVICE	CE SINK IS PROVIDED.			NUMBER OF LAYATORIES	: NSPC TABLE 7.21.1	: (2) MALE, (2) FEMALE	: (2) MALE, (2) FEMALE	ROOF SO	CUTTLE W. GUARD. SEE ROOF PLAN.	HB HOSE BIBB, FROST PROOF EXTERIOR LOCATIONS	AI
				NUMBER OF ACCESSIBLE LAVATORIES	: IBC NJ 2015, 1109.2.3	: (1) PER TOILET FACILITY (4) TOTAL	: (2) MALE, (2) FEMALE (4) TOTAL			+ FD FLOOR DRAIN W/ INLET GR	4TE
ACCESSIBILI	TY NOTES	) •		CLEAR FLOOR AREA	: ICC/ANSI 606.2	: 2'-6" × 4'-0"	: 2'-6" × 4'-0"	ROOF EX	XHAUSTER. SEE ROOF PLAN.	FE 1 FIRE EXTINGUISHER IN SEMI-RECESSED CABINE	T.
										("JL INDUSTRIES - AMBASS #2017-V-10 W/ RED VERTIC,	ADOR",
1. THERE ARE A TOTAL OF (3) TOILET ROOMS IN THE BUIL LOCATED AT THE LOWER LEVEL. A SINGLE USE TOILET			NE.	RIM OR COUNTER HEIGHT	: ICC/ANSI 606.3	: 2'- 0'	: 2'- 0'	ROOF-TO SEE ROO	OP MOUNTED HVAC EQUIPMENT.	FE 2 WALL-MTD., FIRE EXTINGUIS	HER W/ WALL
<ol> <li>ONE DRINKING FOUNTAIN IS PROVIDED FOR THE BUILD!         OBTAINED FROM THE SINK IN KITCHEN 004.</li> </ol>	NG AT THE LOWER LEVEL. ALS	60, DRINKING WATER CAN BE PRO	DVIDED	SIZE OF KNEE SPACE	: ICC/ANSI 606.2	: 2'-6" x 1'-7" x 2'-5" HIGH	: 2'-6" x 1'-7" x 2'-5" HIGH	SEE ROO	=	MOUNT BRACKET AND SIGN  TYPE ABC, MULTI-PURPOSI  DRY CHEMICAL, UL '4A-80	<u>,</u>
3. NEW UNISEX SINGLE USER TOILET ROOM TO BE INSTALLE	ED ON FIRST FLOOR (ROOM 10°	1) WILL BE ACCESSIBLE.		MIRROR MOUNTING HEIGHT (BOTTOM OF REFLECTING SURF.)	: ICC/ANSI 603.3	: 40' MAX.	: 40' MAX.	S FLUE FOI	R FUEL-BURNING APPLIANCE, AUST RISER. SEE MECHANICAL DIUGS	KNOX BOX RAPID ENTRY S	
				NUMBER OF SHOWERS	:	;	: NOT APPLICABLE			#3264, SURFACE-MTD. ALUM TAMPER SWITCH.	
				NUMBER OF ACCESSIBLE SHOWERS	: IBC NJ 2015, 1109.2	: (1) PER BATHING FACILITY	: NOT APPLICABLE	VTR O 3' PLUMI SEE PLU	BIMG VENT THRU-ROOF. IMBING DRAWINGS.	ALUMINUM THRESHOLD	
								-		+ + + + + + MILLINDER BY GC GET DE	TAILS
				DRINKING FOUNTAINS:	CODE SECTION	REQUIREMENT	<u>PROPOSED</u>	1 A-1	DRAWING NUMBER SHEET NUMBER	ON DWG A6-1	·= <del>-</del>
				TOTAL NUMBER PROVIDED	: NSPC TABLE 7.21.1	: 1 PER 100 PEOPLE	: Ø	OFFICE	ROOM NAME ROOM NUMBER	CJ. CONTROL JOINT	
				NO. OF ACCESSIBLE DRINKING FOUNTAINS	: IBC NJ 2015, 1109.5.1	;1	: Ø		COLUMN LINE IDENTIFICATION	LI C.G. INDICATES CORNER OR EN WALL VINYL WALL PROTECT	TION
				CLEAR FLOOR AREA	: ICC/ANSI 6022	: 2'-6" × 4'-Ø"	: 2'-6" × 4'-0"	(A)	NUMBER/LETTER	(INPRO CORPORATION, *13) 3 INCH CORNER GUARD,	0,
				MOUNTING HEIGHT TO SPOUT	: ICC/ANSI 602.4	: 2'-0" \ 4-0"	: 3'-0"		ROOF DETAIL NUMBER.	SURFACE MOUNTED, 8'-0"    (**)FT INDICATES FULLY	HEIGHT)
				I CUNTING REIGHT TO SPOUT	: ICC/ANJI 662.4	: w=v	: J⁼₩	03 - 01 REFERS TO NOTE NUMBE	SPECIFICATION NOTE NUMBER	TEMPERED SAFETY GLAZIN	lG
								REFERS TO SPECIFICATION SEC		FLOOR AND ROOF TRUSS U MOUNTED SIGN	JALL
										HOUNTED SIGN	
										ISSUED FOR BUILDING PERMITS	2
										ISSUED FOR BIDDING	1 - 1 '

S & L A N D P L A N N E
9616 SECOND AVENUE, SUITE 20
STONE HARBOR, NEW JERSEY (
6)-854-0993 WEB: www.oskdp.com
OLIVIERI (1956-1999)
SENIOR ASSOCIATE: DANIEL A. SHOUSKY, AIA, PI
SENIOR ASSOCIATE: DANIEL A. SHOUSKY, AIA, PI

ARCHITE CTS& STANDER: (856)-854-0580
FOUNDER: JOHN J. OLIVIERI (STANDER: JO



**2008** 

IQ3 8 6TH STREET
VINELAND, NEW JERSEY Ø8:

STARTING CONSTRUCTION
STARTING CONSTRUCTION
CERALD S. BLACKMAN JR.

l :			
ERVEC			
RES			
all rights reserved			
L R			
	NO.	DESCRIPTION	DATE
INERS, P.A.		REVISION SCHEDU	ILE
₹ '			

2	REVISION	SCHEDULE
{		
	DRAWN BY:	DC
DESIGN	CHECKED BY:	JSB
5	DATE:	<i>0</i> 3-14-2 <i>0</i> 25
١	SCALE:	AS NOTED

- (A) ALTERATIONS, AS DEFINED IN N.J.A.C. 5:23-6.3, SHALL COMPLY WITH THE REQUIREMENTS OF THIS SECTION.
- (B) ALL WORK SHALL BE DONE IN A WORKMANLIKE MANNER
- (C) THE WORK SHALL NOT CAUSE ANY DIMINUTION OF EXISTING STRUCTURAL STRENGTH, SYSTEM CAPACITY OR MECHANICAL VENTILATION BELOW THAT WHICH EXISTS AT THE TIME OF APPLICATION FOR A PERMIT OR THAT WHICH IS REQUIRED BY THE APPLICABLE SUBCODES OF THE UNIFORM CONSTRUCTION CODE, WHICHEVER IS LOWER. THE REPLACEMENT OR ADDITION OF FIXTURES, EQUIPMENT OR APPLIANCES SHALL NOT INCREASE LOADS ON THESE SYSTEMS UNLESS THE SYSTEM IS UPGRADED IN ACCORDANCE WITH THE APPLICABLE SUBCODE OF THE UCC TO ACCOMMODATE THE INCREASED LOAD.
  - NEWLY INTRODUCED FIXED LOADS SHALL NOT EXCEED THE UNIFORMLY DISTRIBUTED LIVE LOADS OR CONCENTRATED LIVE LOAD CRITERIA OF TABLE 1607.1 OF THE BUILDING SUBCODE OR TABLE R301.5 OF THE ONE- AND TWO-FAMILY DWELLING SUBCODE, AS APPLICABLE, AND SHALL NOT CREATE DEFLECTION THAT EXCEEDS THE STANDARDS SET FORTH AS USED IN THIS SECTION, FIXED LOADS SHALL MEAN UNIFORM OR CONCENTRATED LOADS AND SHALL INCLUDE, BUT NOT BE LIMITED TO, EQUIPMENT, FILES, LIBRARY STACKS, OR SIMILAR LOADING CONDITIONS. (BUILDING)
  - i. FOR WOOD FRAME CONSTRUCTION, DEFLECTION SHALL NOT EXCEED L/180 FOR ROOFS WITH A SLOPE OF 3 IN 12 OR LESS OR L/120 FOR ROOFS WITH A SLOPE OF GREATER THAN 3 IN 12 AND FOR FLOORS.
  - FOR STEEL FRAME CONSTRUCTION, DEFLECTION SHALL NOT EXCEED L/240 FOR ROOFS WITH A SLOPE OF 3 IN 12 OR LESS OR L/180 FOR ROOFS WITH A SLOPE OF GREATER THAN 3 IN 12 AND FOR FLOORS.
  - III. FOR CONCRETE CONSTRUCTION, DEFLECTION SHALL NOT EXCEED L/180 FOR ROOFS OR L/240 FOR FLOORS.
  - FIRE PROTECTION SYSTEM REMOVAL: ANY FIRE PROTECTION SYSTEM PROVIDING PARTIAL OR REDUNDANT PROTECTION ORIGINALLY INSTALLED TO PROTECT A SPECIAL HAZARD THAT NO LONGER EXISTS AND THAT IS NOT REQUIRED IN ACCORDANCE WITH THE CURRENT UNIFORM CONSTRUCTION CODE, IS ALLOWED TO BE REMOVED WITH THE WRITTEN APPROVAL OF THE FIRE SUBCODE OFFICIAL AND FIRE OFFICIAL. ALL DISCONNECTED EQUIPMENT AND DEVICES, SUCH AS PULL STATIONS, NOZZLES, DETECTORS, SPRINKLERS, SENSORS, PANELS AND HOSE CONNECTIONS, SHALL BE REMOVED SO AS NOT TO GIVE A FALSE INDICATION THAT THE STRUCTURE, AREA OR SPACE IS PROTECTED. (FIRE)
  - NO WORK SHALL BE UNDERTAKEN THAT DIMINISHES ACCESSIBILITY BELOW THAT WHICH IS REQUIRED BY CHAPTER II OF THE BUILDING SUBCODE. (BUILDING)
  - CONSTRUCTION MATERIALS USED AS PART OF AN ALTERATION PROJECT SHALL BE CONSISTENT WITH THE EXISTING CONSTRUCTION TYPE OR THE ALLOWABLE CONSTRUCTION TYPE, WHICHEVER IS LESS RESTRICTIVE. (PLAN REVIEW - BUILDING, FIRE. INSPECTION - BUILDING)
- (D) THE FOLLOWING PRODUCTS AND PRACTICES SHALL NOT BE USED:
  - WOOD PANELING BEING USED AS AN INTERIOR FINISH NOT IN CONFORMANCE WITH TABLE 2 OF N.J.A.C. 5:23-6.11 OF THIS SUBCODE + (BUILDING)
  - 2. CARPET USED FOR FLOOR COVERING THAT FAILS TO MEET THE DOC FF-1 "PILL TEST" (CONSUMER PRODUCT SAFETY COMMISSION IS CFR 1630)± (PLAN REVIEW - BUILDING, FIRE. INSPECTION - BUILDING)
  - ELECTRICAL MATERIALS/SUPPLIES: UNLISTED OR UNAPPROVED ELECTRICAL PRODUCTS. AS STATED IN THE NATIONAL ELECTRICAL CODE (SECTIONS 90.1, 1102, 1103, AND ARTICLE 100), ONLY ELECTRICAL PRODUCTS LISTED, LABELED, APPROVED, AND IDENTIFIED ARE ACCEPTABLE. APPROVAL IS TO BE BASED ON TESTS AND LISTINGS OF TESTING LABORATORIES SUCH AS UNDERWRITERS LABORATORIES, INC. (UL.), FACTORY MUTUAL (FM) OR CANADIAN STANDARDS ASSOCIATION/NATIONALLY RECOGNIZED TESTING LABORATORY (CSA/NRTL), ETC.± AND (ELECTRICAL)
  - 4. PLUMBING MATERIALS AND SUPPLIES:
  - i. ALL PURPOSE SOLVENT CEMENT±
  - II. CLEAR PB (POLYBUTYLENE) PIPING±
  - III. FLEXIBLE TRAPS AND TAILPIECES±
  - IV. SHEET AND TUBULAR COPPER AND BRAGG TRAP AND TAILPIECE FITTINGS LEGG THAN B4S (BROWN 4 SHARPE) IT GAUGE (.045 INCH)± AND
  - SOLDER HAVING MORE THAN 02 PERCENT LEAD SHALL NOT BE USED IN THE REPAIR OF POTABLE WATER SYSTEMS. (PLUMBING)
- 5. BARS, GRILLES AND SCREENS SHALL NOT BE PLACED OVER EMERGENCY ESCAPE WINDOWS OR DOORS IN GROUPS R OR I-1 UNLESS THEY ARE RELEASABLE OR REMOVABLE FROM THE INSIDE WITHOUT THE USE OF A KEY, TOOL OR FORCE GREATER THAN THAT WHICH IS REQUIRED FOR THE NORMAL OPERATION OF THE WINDOW OR DOOR (BUILDING)
- 6. THE FOLLOWING PRACTICES SHALL NOT BE USED ON PAINTED SURFACES IN ALL BUILDINGS OF GROUP R THAT WERE CONSTRUCTED BEFORE 1978, GROUP E AND GROUP 1-4 BUILDINGS USED AS CHILD-CARE FACILITIES UNLESS THE PAINTED SURFACE HAS BEEN TESTED AND FOUND TO BE FREE OF LEAD-BASED PAINT:
  - I. OPEN FLAME BURNING OR THE USE OF HIGH TEMPERATURE (IN EXCESS OF 1100 DEGREES FAHRENHEIT)
  - II. POWER SANDING OR SANDBLASTING, UNLESS A SPECIAL HEPA (HIGH EFFICIENCY PARTICULATE AIR) FILTER EQUIPPED VACUUM ATTACHMENT IS USED TO CONTAIN DUST:
  - III. UNCONTAINED WATER BLASTING OR POWER WASHING! OR
  - IV. DRY SCRAPING OR SANDING MORE THAN TWO SQUARE FEET PER ROOM (INTERIOR) OR 10 SQUARE FEET OR MORE PER BUILDING (EXTERIOR). (BUILDING)
  - 1. A MIRROR SHALL NOT BE PLACED IN OR ADJACENT TO ANY MEANS OF EGRESS SO AS TO CONFUSE THE DIRECTION OF EGRESS OR GIVE THE APPEARANCE OF A DOORWAY, EXIT, OR PASSAGEWAY. DRAPERIES OR SIMILAR HANGINGS SHALL NOT OBSCURE AN EXIT. (PLAN REVIEW - BUILDING, FIRE. INSPECTION - BUILDING)
  - i. EXCEPTION: WITHIN DWELLING UNITS OF GROUPS R-2, R-3, R-4 AND R-5.
- (E) THE FOLLOWING PRODUCTS AND PRACTICES SHALL BE REQUIRED, WHEN APPLICABLE:
  - WHEN ANY WATER CLOSET IS REPLACED, THE REPLACEMENT WATER CLOSET SHALL REQUIRE NOT MORE THAN 1.6 GALLONS OF WATER PER FLUSH AS REQUIRED BY THE PLUMBING SUBCODE. (PLUMBING.)
  - IN BUILDINGS REQUIRED BY CHAPTER II OF THE BUILDING SUBCODE TO BE ACCESSIBLE, WHEN BATHROOMS OR TOILET ROOMS ARE ALTERED, THE FOLLOWING REQUIREMENTS FOR PROVIDING ACCESSIBILITY SHALL APPLY UNLESS THE REQUIREMENTS OF CHAPTER II OF THE BUILDING SUBCODE HAVEBEEN MET:
  - WHEN TOILET PARTITIONS ARE MOVED OR INSTALLED, BUT EXISTING FIXTURES ARE NOT BEING MOVED, AN ACCESSIBLE STALL COMPLYING WITH ICC A117.1, SECTION 604.9, SHALL BE CREATED PROVIDED THAT THIS CAN BE ACCOMPLISHED WITHOUT MOVING FIXTURES. (BUILDING)
  - WHEN BATHROOM FIXTURES OR HARDWARE ARE REPLACED, THE REPLACEMENT FIXTURES OR HARDWARE SHALL COMPLY WITH ICC AIIT.I, SECTIONS 603 THROUGH 608, AS APPLICABLE, FOR NONRESIDENTIAL BUILDINGS ORICC AIIT.I, CHAPTER 10, FOR RESIDENTIAL BUILDINGS REQUIRED BY CHAPTER II OF THE BUILDING SUBCODE TO BE ACCESSIBLE. (PLUMBING.)
  - III. WHERE FULL COMPLIANCE IS TECHNICALLY INFEASIBLE, A SINGLE FIXTURE UNISEX ACCESSIBLE BATHROOM SHALL BE PERMITTED. THIS MAY BE ACCOMPLISHED BY PROVIDING TWO UNISEX BATHROOMS, ONE OF WHICH IS ACCESSIBLE. (BUILDING)
  - IV. WHERE IT IS TECHNICALLY INFEASIBLE TO GAIN COMPLIANCE WITH THE ALTERED BATHROOM, SIGNAGE TO THE CLOSEST ACCESSIBLE BATHROOM (IF ANY) SHALL BE PROVIDED AT THE ALTERED BATHROOM. (BUILDING)
- 3. IN BUILDINGS REQUIRED BY CHAPTER 11 OF THE BUILDING SUBCODE TO BE ACCESSIBLE, WHEN SPACE IS RECONFIGURED, THE ALTERED SPACE SHALL COMPLY WITH CHAPTER II OF THE BUILDING SUBCODE. WHERE FULL COMPLIANCE IS TECHNICALLY INFEASIBLE, COMPLIANCE SHALL BE ACHIEVED TO THE MAXIMUM EXTENT FEASIBLE. (BUILDING)
- 4. REPLACEMENT DOORS SHALL COMPLY WITH THE FOLLOWING: (BUILDING)
- IN BUILDINGS REQUIRED BY CHAPTER II OF THE BUILDING SUBCODE TO BE ACCESSIBLE, WHEN NEW DOOR OPENINGS ARE CREATED, EXISTING DOOR OPENINGS ARE ENLARGED OR DOOR ASSEMBLIES ARE REPLACED AND THE REQUIRED DOOR WIDTH CAN BE ACHIEVED WITHIN THE EXISTING OPENING, THE NEW DOOR SHALL COMPLY WITH ICC AIIT.I, SECTION 404. (1) IF THE DOOR BEING ADDED, ENLARGED, OR REPLACED IS A BUILDING ENTRANCE AND AT LEAST 60 PERCENT OF THE ENTRANCE DOORS ARE ACCESSIBLE, THEN THE DOOR BEING ADDED, ENLARGED, OR REPLACED IS NOT REQUIRED TO COMPLY WITH ICC AIIT, I, SECTION 404.

- II. REPLACEMENT DWELLING UNIT, GUEST ROOM OR ROOMING UNIT CORRIDOR DOORS IN GROUPS 1-1, R-1 OR R-2 SHALL BE 13/4 INCH SOLID CORE WOOD OR APPROVED EQUAL WITH APPROVED DOOR CLOSERS AND SHALL NOT HAVE ANY GLASS PANELS, OTHER THAN APPROVED WIRE GLASS IN METAL FRAMES. (1) 13/8 INCH SOLID CORE REPLACEMENT DOORS SHALL BE ACCEPTED IF THE EXISTING FRAME IS NOT BEING REPLACED AND WILL ACCOMMODATE ONLY A 13/8 INCH DOOR
- 5. IN BUILDINGS REQUIRED BY CHAPTER II OF THE BUILDING SUBCODE TO BE ACCESSIBLE, WHEN ENTRANCE STEPS ARE BEING REPLACED, AN ACCESSIBLE ENTRANCE SHALL BE PROVIDED IF THIS DOES NOT ADD MORE THAN 20 PERCENT TO THE COST OF REPLACING THE STEPS. (BUILDING)
  - 1. IF AT LEAST 60 PERCENT OF THE OTHER BUILDING ENTRANCES ARE ACCESSIBLE, THEN THE INSTALLATION OF A RAMP SHALL NOT BE REQUIRED.
- WHEN PROVIDING VERTICAL ACCESS IS PART OF THE SCOPE OF WORK, A LIMITED USE LIMITED APPLICATION ELEVATOR OR PLATFORM LIFT MAY BE INSTALLED AS PERMITTED BY CHAPTER II OF THE BUILDING SUBCODE. (BUILDING)
- REPLACEMENT GLASS SHALL COMPLY WITH THE "SAFETY GLAZING" REQUIREMENTS OF THE BUILDING SUBCODE AND SHALL BE INSTALLED IN THE "HAZARDOUS LOCATIONS" AS SPECIFIED BY SECTIONS 2406.4 AND 2406.5 OF THE BUILDING SUBCODE OR BY SECTION R308.4 OF THE ONE- AND TWO-FAMILY DWELLING SUBCODE, AS APPLICABLE. (BUILDING)
- WHERE A FIREPROOFING MATERIAL IS REMOVED THAT IS INTEGRAL TO THE RATING OF AN EXISTING FIRE-RATED ASSEMBLY, THE MATERIAL SHALL BE REPLACED SO THAT THE RATING IS PRESERVED. (BUILDING)
- PLUG FUSES OF THE EDISON-BASE TYPE SHALL BE USED ONLY FOR REPLACEMENTS WHERE THERE IS NO EVIDENCE OF OVER FUSING OR TAMPERING PER SECTION 240.5(B) OF THE ELECTRICAL SUBCODE. (ELECTRICAL)
- IO. ANY REPLACEMENT TO THE ELECTRICAL SERVICE EQUIPMENT SHALL REQUIRE THAT THE GROUNDING ELECTRODE SYSTEM BE UPDATED TO THE REQUIREMENTS OF ARTICLE 250 PART III OF THE ELECTRICAL SUBCODE. (ELECTRICAL)
- NON-"HOSPITAL GRADE" RECEPTACLES IN PATIENT BED LOCATIONS OF HEALTH CARE FACILITIES, GROUP 1-2, SHALL BE REPLACED WITH 'HOSPITAL GRADE' RECEPTACLES. (ELECTRICAL)
- IN BUILDINGS OF GROUP R OR I-I, WHEN THE WORK BEING PERFORMED CREATES A BEDROOM, THE FOLLOWING SHALL BE PROVIDED: I. A HARD-WIRED SMOKE ALARM SHALL BE INSTALLED WITHIN EACH NEW BEDROOM AND A SECOND, HARD-WIRED SMOKE ALARM SHALL BE INSTALLED WITHIN THE IMMEDIATE VICINITY OF THE BEDROOM IN ACCORDANCE WITH NFPA 12. (FIRE)
  - ii. A BEDROOM WINDOW OR EXTERIOR DOOR THAT MEETS THE REQUIREMENTS AT N.J.A.C. 5:23-6.9(B)/6 SHALL BE PROVIDED WHEN THE BEDROOM CREATED IS BELOW THE FOURTH FLOOR. (BUILDING.) (1) THIS REQUIREMENT SHALL NOT APPLY IN BUILDINGS WHERE THE SLEEPING ROOM IS PROVIDED WITH A DOOR TO A CORRIDOR HAVING ACCESS TO TWO REMOTE EXITS OR IN BUILDINGS EQUIPPED THROUGHOUT WITH AN AUTOMATIC SPRINKLER SYSTEM.
- 13. IN BUILDINGS OF USE GROUPS R-3, R-4, AND R-5:
  - WHEN THE WORK BEING PERFORMED CREATES LIVING SPACE OVER A PRIVATE GARAGE, THE PRIVATE GARAGE SHALL COMPLY WITH SECTION 406.3.2 OF THE BUILDING SUBCODE OR R302.6 OF THE ONE-AND TWO-FAMILY DWELLING SUBCODE, AS APPLICABLE, FOR FIRE RESISTANCE RATING.
  - WHEN THE WORK BEING PERFORMED CREATES AN ADDITIONAL DWELLING UNIT WITHIN THE BUILDING, THE NEW DWELLING UNIT SHALL BE SEPARATED FROM THE EXISTING DWELLING UNIT(S) WITH FIRE PARTITIONS OR HORIZONTAL ASSEMBLIES HAVING A FIRE RESISTANCE RATING OF NOT LESS THAN ONE HOUR CONSTRUCTED IN ACCORDANCE WITH SECTIONS 108 AND 111 OF THE BUILDING SUBCODE OR R302 OF THE ONE- AND TWO-FAMILY DWELLING SUBCODE, AS APPLICABLE.
  - III. WHEN FINISHED SPACE IS CREATED IN PREVIOUSLY UNFINISHED SPACE, RECEPTACLE AND LIGHTING OUTLETS SHALL COMPLY WITH SECTION 210.52 AND 210.70, RESPECTIVELY, OF THE ELECTRICAL
- 14. IN BUILDINGS OF GROUP R-1, IN AT LEAST ONE SLEEPING ROOM OR SUITE OF EVERY 25 OR FEWER THAT ARE PART OF THE SCOPE OF WORK, THE WORK BEING PERFORMED SHALL COMPLY WITH THE APPLICABLE PROVISIONS OF ICC AIIT.I, UNLESS THE FACILITY ALREADY PROVIDES THE NUMBER OF ACCESSIBLE SLEEPING ROOMS REQUIRED BY CHAPTER II OF THE BUILDING SUBCODE. IN ADDITION, AT LEAST ONE SLEEPING ROOM OR SUITE OF EVERY 25 OR FEWER THAT ARE PART OF THE SCOPE OF WORK SHALL BE EQUIPPED WITH A VISUAL ALARM AND NOTIFICATION DEVICE FOR THE HEARING IMPAIRED UNLESS THE FACILITY ALREADY PROVIDES THE NUMBER REQUIRED BY CHAPTER II OF THE BUILDING SUBCODE. (BUILDING)
- 15. IN BUILDINGS OF GROUPS R-1 AND R-2:
  - WHEN HABITABLE SPACE IS CREATED IN PREVIOUSLY UNOCCUPIED SPACE, THE MINIMUM CLEAR CEILING HEIGHT SHALL BE SEVEN FEET. FOR ROOMS WITH A SLOPED CEILING, THE MINIMUM CLEAR CEILING HEIGHT SHALL BE SEVEN FEET FOR AT LEAST 35 SQUARE FEET OF THE FLOOR AREA OF THE ROOM. ANY PORTION OF THE ROOM MEASURING LESS THAN FIVE FEET FROM THE FINISHED FLOOR TO THE FINISHED CEILING SHALL NOT BE CONSIDERED USABLE FLOOR AREA. (PLAN REVIEW - BUILDING, FIRE. INSPECTION
  - II. GROUP R-2 ONLY: WHEN FINISHED SPACE IS CREATED IN PREVIOUSLY UNFINISHED SPACE, RECEPTACLE AND LIGHTING OUTLETS SHALL COMPLY WITH SECTION 210.52 AND 210.70, RESPECTIVELY, OF THE
- WHEN A NEW REFRIGERANT IS INTRODUCED, THE REQUIREMENTS OF THE MECHANICAL SUBCODE APPLICABLE TO THAT REFRIGERANT, IF ANY, SHALL BE MET. THIS SHALL APPLY TO THE INSTALLATION OF NEW EQUIPMENT, THE REPLACEMENT OF EXISTING EQUIPMENT WITH EQUIPMENT USING A DIFFERENT REFRIGERANT, OR THE REPLACEMENT OF THE REFRIGERANT IN EXISTING EQUIPMENT WITH A DIFFERENT REFRIGERANT. (PLUMBING)
- 17. WHEN THE WORK BEING PERFORMED CREATES OR EXPOSES WOOD FRAMING OF ANY WALL, FLOOR, CEILING, OR ROOF, FIREBLOCKING SHALL BE PROVIDED AS REQUIRED BY SECTION 1182 OF THE BUILDING SUBCODE OR SECTION R3/02.11 OF THE ONE- AND TWO-FAMILY DWELLING SUBCODE, AS APPLICABLE. THE FIREBLOCKING MATERIAL SHALL COMPLY WITH SECTION 1182.1 OF THE BUILDING SUBCODE OR SECTION R302.11.1 OF THE ONE-AND TWO-FAMILY DWELLING SUBCODE, AS APPLICABLE.
- 18. WHEN THE WORK BEING PERFORMED CREATES OR EXPOSES THE ROOF DECKING/SHEATHING OR THE FRAMING OF ANY WALL, FLOOR, CEILING, OR ROOF ASSEMBLY THAT IS PART OF THE BUILDING THERMAL ENVELOPE (ENCLOSES CONDITIONED SPACE), ANY ACCESSIBLE VOIDS IN INSULATION SHALL BE FILLED USING INSULATION MEETING THE RYALUES OF TABLE R402.12 (NII02.12) OF THE RESIDENTIAL ENERGY CODE FOR WOOD FRAMING AND OF TABLE R40226 (NII0226) OF THE RESIDENTIAL ENERGY CODE FOR METAL FRAMING EQUIVALENTS OR OF TABLE 5.5-4 OR 5.5-5 OF THE COMMERCIAL ENERGY CODE, AS APPLICABLE.
- IN THE EVENT THAT INSULATION MEETING THE R-VALUES ABOVE CANNOT BE INSTALLED DUE TO SPACE CONSTRAINTS, AND THE EQUIVALENCY EXCEPTIONS OF SECTIONS R4022.1 AND R4022.2 (NII022.1 AND NII0222) CANNOT BE APPLIED FOR RESIDENTIAL BUILDINGS, INSULATION THAT FILLS THE CAVITIES OF THE FRAMED ASSEMBLY SHALL BE INSTALLED.
- WHEN FENESTRATION (WINDOWS, SKYLIGHTS, OR DOORS) IS NEWLY INSTALLED OR REPLACED, THE U-FACTOR (THERMAL TRANSMITTANCE) SHALL NOT EXCEED THE U-FACTOR OF TABLE R402.12 (NII02.12) OF THE REGIDENTIAL ENERGY CODE OR OF TABLE 5.5-4 OR 5.5-5 OF THE COMMERCIAL ENERGY CODE, AS
- I. EXCEPTION: IN RESIDENTIAL BUILDINGS, FENESTRATION THAT MEETS SECTIONS R402.3.3 (NIIØ2.3.3) AND R4Ø2.3.4 (NIIØ2.3.4), AS APPLICABLE.
- 20. DUCTS THAT ARE NEWLY INSTALLED OR REPLACED SHALL BE INSTALLED WITH INSULATION MEETING THE R-VALUES OF SECTION R403.3.1 (NII03.3.1) OF THE RESIDENTIAL ENERGY CODE OR OF SECTION 6.4.4.1.2 OF THE COMMERCIAL ENERGY CODE, AS APPLICABLE.
- THE TOTAL REPLACEMENT OF A BUILDING LIGHTING SYSTEM OR A NEWLY INSTALLED BUILDING LIGHTING SYSTEM SHALL MEET SECTION R404 (NII04) OF THE RESIDENTIAL ENERGY CODE OR SECTION 9.12 OF THE COMMERCIAL ENERGY CODE, AS APPLICABLE. (A "LIGHTING SYSTEM" IS DEFINED BY THE COMMERCIAL ENERGY CODE AS 'A GROUP OF LUMINAIRES CIRCUITED OR CONTROLLED TO PERFORM A SPECIFIC FUNCTION.")
  - EXCEPTION: THE TOTAL REPLACEMENT OF A LIGHTING SYSTEM WITHIN A ROOM, SPACE OR TENANCY SHALL BE REQUIRED TO MEET SECTION 9.1.2 FOR THE ROOM, SPACE, OR TENANCY ONLY.
- 22. WHEN THE WORK BEING PERFORMED RESULTS IN AN INDOOR OR OUTDOOR GAS METER, RELATED REGULATOR OR PIPING BECOMING SUBJECT TO VEHICLE IMPACT, WHICH WORK INCLUDES, BUT IS NOT LIMITED TO, NEW INSTALLATION, RELOCATION OR OTHER CONSTRUCTION, THE GAS METER, RELATED REGULATOR OR PIPING SHALL BE PROTECTED BY BARRIERS MEETING THE REQUIREMENTS OF SECTION 312 OF THE INTERNATIONAL FIRE CODE. FOR THE PURPOSE OF APPLYING THIS PROVISION, "SUBJECT TO VEHICLE IMPACT" SHALL MEAN LOCATED WITHIN THREE FEET OF ANY GARAGE DOOR OPENING, DRIVEWAY OR DESIGNATED PARKING AREA AND NOT SEPARATED BY A BUILDING WALL FROM THE SPACE WHERE A VEHICLE MAY BE OPERATED.
  - I. EXCEPTION: IF VERIFICATION OF THE INSTALLATION OF AN EXCESS FLOW VALVE IS PROVIDED BY THE GAS UTILITY, VEHICLE IMPACT BARRIERS SHALL NOT BE REQUIRED.

- 23. WHERE WORK, OTHER THAN ORDINARY MAINTENANCE OR MINOR WORK, IS BEING PERFORMED ON AN ELEVATOR, THE ELEVATOR SHALL BE EQUIPPED TO OPERATE WITH A STANDARDIZED FIRE SERVICE KEY.
- 24. THE WORK SHALL NOT CAUSE AN EXIT ENCLOSURE TO BE USED FOR ANY PURPOSE OTHER THAN MEANS OF EGRESS, EXCEPT THOSE PENETRATIONS PERMITTED BY SECTION 1023.5 OF THE BUILDING SUBCODE.
- 25. EXISTING OPENINGS THAT BECOME PART OF AN EXIT OR EXIT ACCESS AND NEWLY CREATED OPENINGS TO BE USED AS AN EXIT OR EXIT ACCESS SHALL MEET SECTION 10/08.3 AND SECTION 10/13 OF THE BUILDING SUBCODE WHEN MORE THAN ONE EXIT OR EXIT ACCESS IS REQUIRED. THIS SHALL APPLY ONLY TO THE PORTION OF THE BUILDING SERVED BY THE NEW EXIT OR EXIT ACCESS.
- (F) IN BUILDINGS OF GROUPS R-3, R-4, AND R-5 AND IN DWELLING UNITS OF GROUP R-2, SMOKE ALARMS SHALL BE INSTALLED AND MAINTAINED ON EACH LEVEL OF THE STRUCTURE, OUTSIDE EACH SEPARATE SLEEPING AREA IN THE IMMEDIATE VICINITY OF THE BEDROOMS, AND LOCATED ON OR NEAR THE CEILING. BATTERY-OPERATED UNITS SHALL BE PERMITTED, BUT SHALL NOT REPLACE ANY AC-POWERED SMOKE ALARMS OR A HOUSEHOLD FIRE ALARM SYSTEM. (FIRE)
- (G) IN BUILDINGS CONTAINING A FUEL BURNING APPLIANCE OR HAVING AN ATTACHED GARAGE, CARBON MONOXIDE DETECTION EQUIPMENT SHALL BE INSTALLED IN ACCORDANCE WITH SECTION 915 OF THE BUILDING SUBCODE OR SECTION R315 OF THE ONE- AND TWO-FAMILY DWELLING SUBCODE, AS APPLICABLE. (FIRE)
  - EXCEPTION: BATTERY-POWERED OR PLUG-IN DEVICES SHALL BE ACCEPTED FOR PURPOSES OF MEETING THE REQUIREMENTS OF THIS SECTION.
- (H) THE WORK SHALL NOT MAKE THE BUILDING LESS CONFORMING WITH THE BASIC REQUIREMENTS OF THIS SUBCHAPTER THAN IT WAS WHEN THE ALTERATION WAS UNDERTAKEN.
  - WHERE THE BUILDING CURRENTLY EXCEEDS THE BASIC REQUIREMENTS, THE EXTENT TO WHICH IT EXCEEDS SHALL NOT BE REDUCED UNLESS THE BUILDING ALSO EXCEEDS THE REQUIREMENTS OF THE CORRESPONDING SUBCODE OF THE UCC. IN THIS CASE, THE EXTENT OF COMPLIANCE WITH THE BASIC REQUIREMENTS MAY BE REDUCED, BUT NOT BELOW THE REQUIREMENTS OF THE CORRESPONDING SUBCODE OF THE UCC.
  - WHERE THE SCOPE OF WORK CONSISTS OF AN ITEM FOR WHICH REQUIREMENTS ARE ESTABLISHED IN THE BASIC REQUIREMENTS OF THIS SUBCODE, THE WORK SHALL COMPLY WITH THE BASIC REQUIREMENTS.
- (1) ALL MATERIALS AND METHODS USED SHALL COMPLY WITH THE REQUIREMENTS SPECIFIED IN N.J.A.C. 5:23-6.8, MATERIALS AND METHODS.
- EXCEPTION: WINDOWS MAY BE REPLACED WITH WINDOWS LIKE THOSE EXISTING WITHOUT MEETING THE SIZE REQUIREMENTS OF THE BUILDING SUBCODE.
  - IN SLEEPING ROOMS BELOW THE FOURTH STORY IN OCCUPANCIES OF GROUPS R OR 1-1, WHERE NEW WINDOW OPENINGS ARE BEING CREATED OR THE SIZE OF WINDOW OPENINGS IS BEING CHANGED, AT LEAST ONE WINDOW SHALL:

    - (2) HAVE A SILL HEIGHT OF NOT MORE THAN 44 INCHES! (3) HAVE A WIDTH OF AT LEAST 20 INCHES, A HEIGHT OF AT LEAST 24 INCHES AND A MINIMUM TOTAL AREA OF 5.7 SQUARE FEET MEASURED FROM HEAD TO SILL AND FROM SIDE TO SIDE.
- (4) NEW WINDOW OPENINGS IN SLEEPING ROOMS SHALL NOT BE REQUIRED TO MEET THESE REQUIREMENTS IN BUILDINGS WHERE THE SLEEPING ROOM IS PROVIDED WITH A DOOR TO A CORRIDOR HAVING ACCESS TO TWO REMOTE EXITS OR IN BUILDINGS EQUIPPED THROUGHOUT WITH AN AUTOMATIC SPRINKLER SYSTEM.
  - BASEMENT WINDOWS IN BUILDINGS OF GROUP R-2 SHALL COMPLY WITH THE REQUIREMENTS OF N.J.A.C. 5:23-6.26(B)3 WHERE THE WINDOW SERVES AS THE SECOND MEANS OF EGRESS FROM THE DWELLING UNIT (PLAN REVIEW - BUILDING, FIRE, INSPECTION - BUILDING).
- 2. NEWLY INSTALLED AND REPLACEMENT HANDRAILS AND GUARDRAILS SHALL COMPLY WITH SECTIONS 1011.11, 1012.8, 1014, AND 1015 OF THE BUILDING SUBCODE, RESPECTIVELY, OR SECTIONS R311.7.8, R311.8.3, AND R312.1 OF THE ONE- AND TWO-FAMILY DWELLING SUBCODE, RESPECTIVELY, AS APPLICABLE. WHERE 50 PERCENT OR MORE OF A HANDRAIL OR GUARDRAIL ON A FLIGHT OR ON A LEVEL IS REPLACED, THEN THIS SHALL BE CONSIDERED A COMPLETE REPLACEMENT AND SHALL COMPLY WITH THE ABOVE REFERENCED SECTIONS. THE REPAIR OR REPLACEMENT OF LESS THAN 50 PERCENT OF A HANDRAIL OR GUARDRAIL SHALL BE PERMITTED TO MATCH THE EXISTING HANDRAIL OR GUARDRAIL. (BUILDING)
- (J) ALL NEW BUILDING ELEMENTS, AS LISTED IN N.J.A.C. 5:23-6.9, SHALL COMPLY WITH THE REQUIREMENTS OF THAT
- (K) IN A BUILDING REQUIRED BY CHAPTER 11 OF THE BUILDING SUBCODE TO BE ACCESSIBLE, WHERE THE SPACE ALTERED IS A PRIMARY FUNCTION SPACE, AN ACCESSIBLE PATH OF TRAVEL TO THE ALTERED SPACE SHALL BE PROVIDED UP TO THE POINT AT WHICH THE COST OF PROVIDING ACCESSIBILITY IS DISPROPORTIONATE TO THE COST OF THE OVERALL ALTERATION PROJECT: A COST IS DISPROPORTIONATE IF IT EXCEEDS 20 PERCENT OF THE COST OF THE ALTERATION WORK. (BUILDING)
  - THE ACCESSIBLE PATH OF TRAVEL SHALL INCLUDE, BUT NOT BE LIMITED TO, AN ACCESSIBLE PARKING SPACE, AN ACCESSIBLE EXTERIOR ROUTE, AN ACCESSIBLE BUILDING ENTRANCE, AN ACCESSIBLE INTERIOR ROUTE TO THE ALTERED AREA, ACCESSIBLE RESTROOMS, ACCESSIBLE DRINKING FOUNTAINS, AND ACCESSIBLE TELEPHONES SERVING THE ALTERED PRIMARY FUNCTION SPACE, PRIORITY SHALL BE GIVEN TO PROVIDING AN ACCESSIBLE ENTRANCE OR ACCESSIBLE RESTROOMS WHERE POSSIBLE.
- 2. IN DETERMINING DISPROPORTIONATE COST, THE FOLLOWING MATERIALS MAY BE DEDUCTED FROM THE OVERALL COST OF THE PROJECT:
  - WINDOWS, HARDWARE, OPERATING CONTROLS, ELECTRICAL OUTLETS AND SIGNAGE±
  - MECHANICAL SYSTEMS, ELECTRICAL SYSTEMS, INSTALLATIONS OR ALTERATIONS OF FIRE PROTECTION SYSTEMS OR ABATEMENT OF HAZARDOUS MATERIALS + OR
- III. THE REPAIR OR INSTALLATION OF ROOFING, SIDING, OR OTHER EXTERIOR WALL FACADE. WHERE THE WORK CONSISTS SOLELY OF THE ALTERATION OF MATERIALS OR SYSTEMS LISTED IN (K)2 ABOVE,
- THE PATH OF TRAVEL REQUIREMENTS SHALL NOT APPLY. 4. WHERE THE ALTERATION WORK IS FOR THE PRIMARY PURPOSE OF INCREASING THE ACCESSIBILITY OF THE
- BUILDING OR TENANCY, THE REQUIREMENT TO FURTHER IMPROVE THE PATH OF TRAVEL SHALL NOT APPLY.
- WHERE IT IS TECHNICALLY INFEASIBLE TO COMPLY WITH THE TECHNICAL STANDARDS IN CHAPTER II OF THE BUILDING SUBCODE, THE WORK MUST COMPLY TO THE MAXIMUM EXTENT FEASIBLE.
- (L) WHEN WORK IS PERFORMED IN A CLASS I STRUCTURE OR WHEN WORK IS PERFORMED ON A SMOKE CONTROL SYSTEM, A LIST OF ALL MATERIALS AND WORK REQUIRING SPECIAL INSPECTIONS, AND A LIST OF AGENCIES, QUALIFIED LICENSED PROFESSIONALS OR FIRMS INTENDED TO BE RETAINED FOR CONDUCTING THOSE INSPECTIONS IN ACCORDANCE WITH THE REQUIREMENTS OF THE BUILDING SUBCODE SHALL BE SUBMITTED AS PART OF THE PERMIT APPLICATION. (BUILDING, EXCEPT SMOKE CONTROL SYSTEMS - FIRE)
- § 5:23-6.14 BASIC REQUIREMENTS--GROUPS A-2 OTHER THAN NIGHTCLUBS, A-3 AND A-4
- (A) AUTOMATIC SPRINKLER SYSTEM: AN AUTOMATIC SPRINKLER SYSTEM SHALL BE REQUIRED IN SPACES OF GROUP A-3 USED AS BALLROOMS, EXHIBIT AREAS AND ACCESSORY SPACES WHICH EXCEED 12,000 SQUARE FEET AND ARE LOCATED IN BUILDINGS OF GROUP R-1 AND R-2.
  - 1. EXCEPTIONS:
    - AN AUTOMATIC SPRINKLER SYSTEM SHALL NOT BE REQUIRED IF THE SPACE IS DIVIDED INTO FIRE AREAS OF NOT MORE THAN 12,000 SQUARE FEET BY A TWO-HOUR FIRE SEPARATION WITH 1 1/2-HOUR OPENING PROTECTIVES OR IF THE SPACE IS COMPLETELY SEPARATED FROM ANY OTHER USES BY A TWO-HOUR FIRE SEPARATION WITH 1 1/2- HOUR OPENING PROTECTIVES. (FIRE)
- (B) EXITS: TWO EXITS SHALL BE REQUIRED FOR STORIES WITH LESS THAN 500 OCCUPANTS. THREE EXITS SHALL BE REQUIRED FOR STORIES WITH 501 TO 1,000 OCCUPANTS. FOUR EXITS SHALL BE REQUIRED FOR STORIES WITH MORE THAN 1,000 OCCUPANTS. TWO MEANS OF EGRESS ARE ALSO REQUIRED FROM ALL MEZZANINES WITH AN OCCUPANT LOAD GREATER THAN 50 OR WITH EXIT TRAVEL DISTANCE GREATER THAN 15 FEET.
  - WHEN MORE THAN ONE EXIT IS REQUIRED, EXISTING FIRE ESCAPES SHALL BE ACCEPTED AS PROVIDING ONE OF THE REQUIRED MEANS OF EGRESS UNLESS JUDGED TO BE DANGEROUS FOR USE UNDER EMERGENCY EXITING CONDITIONS. FOR USE OF FIRE ESCAPES, ACCESS SHALL BE THROUGH A DOOR EXCEPT WHEN SERVING AN OCCUPANT LOAD OF 10 OR FEWER. ALL OCCUPANTS SHALL HAVE UNOBSTRUCTED ACCESS TO FIRE ESCAPES WITHOUT HAVING TO PASS THROUGH A ROOM SUBJECT TO LOCKING.
    - WHEN MORE THAN ONE EXIT IS REQUIRED AND THERE IS NOT SUFFICIENT SPACE FOR AN EXTERIOR STAIR WITHIN THE LOT LINE, A NEW FIRE ESCAPE SHALL BE ACCEPTED AS PROVIDING ONE OF THE REQUIRED MEANS OF EGRESS. NEWLY-INSTALLED FIRE ESCAPES SHALL COMPLY WITH FTO-3.
  - LADDERS SHALL BE PROHIBITED ON FIRE ESCAPES USED AS A REQUIRED MEANS OF EGRESS.

- 2. A SINGLE EXIT IS PERMITTED IN THE STORY AT THE LEVEL OF EXIT DISCHARGE WHEN THE OCCUPANT LOAD OF THE STORY DOES NOT EXCEED 50 AND THE EXIT ACCESS TRAVEL DISTANCE DOES NOT EXCEED 15 FEET. (PLAN REVIEW--BUILDING, FIRE. INSPECTION--BUILDING)
- (C) EGRESS DOORWAYS: A MINIMUM OF TWO EGRESS DOORWAYS SHALL BE REQUIRED FOR ALL ROOMS AND SPACES WITH AN OCCUPANT LOAD GREATER THAN 50 OR IN WHICH THE TRAVEL DISTANCE EXCEEDS 15 FEET. ALL EGRESS DOORS SERVING AN OCCUPANT LOAD GREATER THAN 50 SHALL SWING IN THE DIRECTION OF EXIT TRAVEL.
- EXCEPTION: STORAGE ROOMS WITH A MAXIMUM OCCUPANT LOAD OF 10 SHALL NOT BE REQUIRED TO HAVE TWO EGRESS DOORWAYS.
- 2. ALL REQUIRED EXIT DOORS EQUIPPED WITH LATCHING DEVICES IN BUILDINGS OR SPACES WITH AN OCCUPANT LOAD GREATER THAN 100 SHALL BE EQUIPPED WITH APPROVED PANIC HARDWARE. 3. IF THERE ARE MORE THAN TWO INDIVIDUAL ROOMS WHICH CAN BE USED FOR SEPARATE FUNCTIONS, EACH WITH AN OCCUPANT LOAD OF MORE THAN 300, THE REQUIRED EGRESS DOORS FROM SUCH ROOMS SHALL LEAD DIRECTLY OUTSIDE OR TO AN EXIT PASSAGEWAY. EXIT PASSAGEWAYS SHALL BE COMPLETELY ENCLOSED BY ASSEMBLIES HAVING A FIRERESISTANCE RATING OF AT LEAST TWO HOURS, SHALL LEAD DIRECTLY OUTSIDE AND SHALL NOT BE USED FOR ANY OTHER PURPOSE. (PLAN REVIEW--BUILDING, FIRE. INSPECTION--BUILDING.)
- (D) CAPACITY OF MEANS OF EGRESS: THE CAPACITY OF THE MEANS OF EGRESS IN EACH WORK AREA SHALL BE DETERMINED IN ACCORDANCE WITH N.J.A.C. 5:23-6.11(B). ADDITIONALLY, FOR BUILDINGS WITH AN OCCUPANT LOAD OF 100 OR MORE, A MAIN ENTRANCE CAPABLE OF SERVING AS THE MAIN EXIT WITH AN EGRESS CAPACITY FOR AT LEAST ONEHALF THE TOTAL OCCUPANT LOAD IS REQUIRED. THE REMAINING EXITS SHALL BE CAPABLE OF PROVIDING ONE-HALF OF THE TOTAL REQUIRED EXIT CAPACITY. THIS PROVISION SHALL NOT APPLY IN BUILDINGS WITH MULTIPLE MAIN ENTRANCES. (PLAN REVIEW-BUILDING, FIRE. INSPECTION-BUILDING.)
- (E) DEAD END CORRIDORS: EXISTING DEAD END CORRIDORS SHALL NOT EXCEED 35 FEET IN LENGTH. EXCEPTIONS ARE AS FOLLOWS:
- DEAD END CORRIDORS MAY BE UP TO 50 FEET IN LENGTH IN A BUILDING WITH AN AUTOMATIC ALARM SYSTEM INSTALLED IN CONFORMANCE WITH THE BUILDING CODE IN EFFECT AT THE TIME OF ITS INSTALLATION.
- DEAD END CORRIDORS MAY BE UP TO 10 FEET IN LENGTH IN A BUILDING WITH AN AUTOMATIC SPRINKLER SYSTEM INSTALLED IN CONFORMANCE WITH THE BUILDING CODE IN EFFECT AT THE TIME OF ITS INSTALLATION. (PLAN REVIEW--BUILDING, FIRE. INSPECTION--BUILDING)
- (F) MEANS OF EGRESS LIGHTING: ARTIFICIAL LIGHTING WITH AN INTENSITY OF NOT LESS THAN ONE FOOT CANDLE AT FLOOR LEVEL SHALL BE REQUIRED DURING ALL TIMES THAT THE CONDITIONS OF OCCUPANCY OF THE BUILDING REQUIRE THAT THE EXITS BE AVAILABLE. LIGHTING SHALL ALSO BE REQUIRED TO ILLUMINATE THE EXIT DISCHARGE. IN ALL BUILDINGS, ROOMS OR SPACES REQUIRED TO HAVE MORE THAN ONE EXIT OR EXIT ACCESS, MEANS OF EGRESS LIGHTING SHALL BE CONNECTED TO AN EMERGENCY ELECTRICAL SYSTEM CONFORMING TO NFPA 10 (NEC) EXCEPT THAT CONTINUED ILLUMINATION SHALL BE REQUIRED TO BE PROVIDED FOR NOT LESS THAN ONE HOUR IN THE CASE OF PRIMARY POWER LOSS.
  - IN BUILDINGS USED FOR MOTION PICTURES OR OTHER PROJECTIONS BY MEANS OF DIRECTED LIGHT, THE ILLUMINATION OF AISLES MAY BE REDUCED DURING PERIODS OF PROJECTION TO NOT LESS THAN 02 FOOT CANDLE. THE SWITCH REQUIREMENTS AND LOCATION(S) FOR CONTROLLING EGRESS LIGHTING CONNECTED TO THE EMERGENCY ELECTRICAL SYSTEM SHALL BE IN CONFORMANCE WITH THE NFPA 10 (NEC.). (PLAN REVIEW--BUILDING, FIRE, ELECTRIC. INSPECTION--BUILDING)
- (G) ILLUMINATED EXIT SIGNS: ILLUMINATED EXIT SIGNS SHALL BE PROVIDED FOR ALL REQUIRED MEANS OF EGRESS IN ALL BUILDINGS, ROOMS OR SPACES REQUIRED TO HAVE MORE THAN ONE EXIT OR EXIT ACCESS. EXIT SIGNS SHALL BE VISIBLE FROM THE EXIT ACCESS AND SUPPLEMENTED BY DIRECTIONAL SIGNS WHEN NECESSARY. (EXCEPTION: APPROVED MAIN EXTERIOR DOORS THAT ARE CLEARLY IDENTIFIED AS EXITS ARE NOT REQUIRED TO HAVE EXIT SIGNS.) EXIT SIGNS SHALL MEET THE FOLLOWING CRITERIA:
  - RED OR GREEN LETTERS AT LEAST SIX INCHES HIGH± MINIMUM WIDTH OF EACH STROKE 3/4 INCH ON A WHITE BACKGROUND OR IN OTHER APPROVED DISTINGUISHABLE COLORS. ARROWS, IF PROVIDED, SHALL BE SUCH THAT THE DIRECTION CANNOT READILY BE CHANGED. THE WORD "EXIT" SHALL BE CLEARLY DISCERNIBLE WHEN THE SIGN IS NOT ENERGIZED. EXIT SIGNS SHALL BE ILLUMINATED AT ALL TIMES WHEN THE BUILDING IS OCCUPIED BY A SOURCE PROVIDING
- AT LEAST FIVE FOOT CANDLES AT THE ILLUMINATED SURFACE OR SHALL BE APPROVED SELF-LUMINOUS SIGNS WHICH PROVIDE EVENLY ILLUMINATED LETTERS WITH A MINIMUM LUMINANCE OF 0.06 FOOT LAMBERTS. EXIT SIGNS SHALL BE CONNECTED TO AN EMERGENCY ELECTRICAL SYSTEM CONFORMING TO NFPA 10 (NEC) EXCEPT THAT CONTINUED ILLUMINATION SHALL BE REQUIRED TO BE PROVIDED FOR NOT LESS THAN ONE HOUR IN THE CASE OF PRIMARY POWER LOSS, NO EMERGENCY POWER SHALL BE REQUIRED FOR APPROVED SELF-LUMINOUS SIGNS. (PLAN REVIEW-BUILDING, FIRE. INSPECTION-BUILDING)
- HANDRAILS OR IN WHICH THE EXISTING HANDRAILS ARE IN DANGER OF COLLAPSING WHEN USED UNDER EMERGENCY EXITING CONDITIONS, SHALL BE PROVIDED WITH HANDRAILS FOR THE FULL LENGTH OF THE RUN OF STEPS ON AT LEAST ONE SIDE. ALL EXIT STAIRWAYSMORE THAN 66 INCHES WIDE SHALL HAVE HANDRAILS ON BOTH SIDES UNLESS THE FULL WIDTH OF THE STAIRWAY IS NOT NEEDED TO ACCOMMODATE THE DESIGN OCCUPANCY. (PLAN REVIEW--BUILDING, FIRE. INSPECTION--BUILDING)

(H) HANDRAILS: EVERY REQUIRED EXIT STAIRWAY HAVING THREE OR MORE RISERS AND NOT PROVIDED WITH

- GUARDS: EVERY OPEN PORTION OF A STAIR, LANDING OR BALCONY WHICH IS MORE THAN 30 INCHES ABOVE THE FLOOR OR GRADE BELOW AND IS NOT PROVIDED WITH GUARDS OR THOSE IN WHICH THE EXISTING GUARDS ARE IN DANGER OF COLLAPSING WHEN USED UNDER EMERGENCY EXITING CONDITIONS, SHALL BE PROVIDED WITH GUARDS. (PLAN REVIEW--BUILDING, FIRE. INSPECTION--BUILDING)
- (J) YERTICAL OPENING PROTECTION: YERTICAL OPENING PROTECTION FOR INTERIOR STAIRWAYS AND OTHER VERTICAL OPENINGS SHALL BE PROVIDED AS FOLLOWS:
  - FOR VERTICAL OPENINGS CONNECTING MORE THAN SIX FLOOR LEVELS, APPROVED ASSEMBLIES HAVING A FIRE RESISTANCE RATING OF NOT LESS THAN TWO HOURS WITH APPROVED OPENING PROTECTIVES SHALL BE
  - FOR VERTICAL OPENINGS CONNECTING FOUR TO SIX FLOOR LEVELS, APPROVED ASSEMBLIES HAVING A FIRE RESISTANCE RATING OF NOT LESS THAN ONE HOUR WITH APPROVED OPENING PROTECTIVES SHALL BE
- FOR VERTICAL OPENINGS NOT EXCEEDING THREE STORIES, A MINIMUM 30-MINUTE UFC FIRE BARRIER SHALL BE REQUIRED. EXCEPTIONS ARE AS FOLLOWS:
  - I. WHEN CONNECTING THE MAIN FLOOR AND MEZZANINES OR
  - ii. WHEN ALL OF THE FOLLOWING CONDITIONS ARE MET:
    - (1) THE COMMUNICATING AREA HAS A LOW HAZARD OCCUPANCY OR HAS A MODERATE HAZARD OCCUPANCY WHICH IS PROTECTED THROUGHOUT BY AN AUTOMATIC SPRINKLER SYSTEM±
    - (2) THE LOWEST OR NEXT TO THE LOWEST LEVEL IS A STREET FLOOR!
    - (3) THE ENTIRE AREA IS OPEN AND UNOBSTRUCTED IN A MANNER SUCH THAT IT MAY BE ASSUMED THAT A FIRE IN ANY PART OF THE INTERCONNECTED SPACES WILL BE READILY OBVIOUS TO ALL
    - (4) EXIT CAPACITY IS SUFFICIENT TO PROVIDE EGRESS SIMULTANEOUSLY FOR ALL THE OCCUPANTS OF ALL LEVELS BY CONSIDERING ALL AREAS TO BE A SINGLE FLOOR AREA FOR THE DETERMINATION OF REQUIRED EXIT CAPACITY AND
    - (5) EACH FLOOR LEVEL, CONSIDERED SEPARATELY, HAS AT LEAST ONE-HALF OF ITS INDIVIDUAL REQUIRED EXIT CAPACITY PROVIDED BY AN EXIT OR EXITS LEADING DIRECTLY OUT OF THAT LEVEL WITHOUT HAVING TO TRAVERSE ANOTHER COMMUNICATING FLOOR LEVEL OR BE EXPOSED TO THE SMOKE OR FIRE SPREADING FROM ANOTHER COMMUNICATING FLOOR LEVEL. (PLAN REVIEW--BUILDING, FIRE. INSPECTION-- BUILDING)
- (K) STRUCTURAL ELEMENTS: STRUCTURAL ELEMENTS WHICH ARE UNCOVERED DURING THE COURSE OF THE REHABILITATION AND WHICH ARE FOUND TO BE UNSOUND OR OTHERWISE STRUCTURALLY DEFICIENT, SHALL BE REINFORCED, SUPPORTED OR REPLACED IN ACCORDANCE WITH THE APPLICABLE STRUCTURAL DESIGN CRITERIA OF THE BUILDING SUBCODE. WHERE STRUCTURAL ELEMENTS ARE SOUND, THERE IS NO EXCESSIVE DEFLECTION (DEFINED AS DEFLECTION IN EXCESS OF THE STANDARDS SET FORTH IN N.J.A.C. 5:23-6.7(C)1), AND FIXED LOADS ARE NOT CHANGING IN A WAY THAT WILL INCREASE THE STRESSES ON EXISTING STRUCTURES BEYOND THAT WHICH IS PERMITTED BY N.J.A.C. 5:23-6.7(C), EXISTING STRUCTURAL ELEMENTS SHALL BE PERMITTED TO REMAIN. (BUILDING)
- (L) PLUMBING FIXTURES: THE FOLLOWING APPLY TO PLUMBING FIXTURES: (PLUMBING)
  - FOR AUDITORIUMS, MUSEUMS, LIBRARIES, AND SIMILAR FACILITIES, PLUMBING FIXTURES SHALL BE PROVIDED AS FOLLOWS. WHERE THE PLUMBING SUBCODE ALLOWS FOR THE SUBSTITUTION OR OMISSION OF FIXTURES, SUCH SUBSTITUTIONS OR OMISSIONS SHALL ALSO BE PERMITTED UNDER THIS SECTION.


ISSUED FOR BUILDING PERMITS Ø4-1Ø-2 ISSUED FOR BIDDING 01-08-25 DRAWING ISSUE

TNE

40

PA N N SO H


S



DESCRIPTION

REVISION SCHEDULE DRAWN BY: DC CHECKED BY: JSB *Ø*3-14-2*Ø*25 AS NOTED

JOB NO. 2199.01



a

DESCRIPTION

REVISION SCHEDULE DC

CHECKED BY: JSB 01-08-2025 1/8" = 1'-0"


> 2199.01 **SP** = 1

<u>No.</u>


- ALL DIMENSIONS TO BE FIELD VERIFIED BEFORE THE START OF CONSTRUCTION. NOTIFY ARCHITECT OF ANY DISCREPANCIES.
- 2. ALL AREAS AFFECTED BY CONSTRUCTION OR DEMOLITION TO BE REPAIRED. PATCH, REPAIR, AND RE-FINISH ENTIRE SURFACE OF ALL WALLS, FLOORS, AND CEILINGS DISTURBED BY NEW WORK. FINISH TO MATCH EXISTING. ALL NEW WORK SHALL BE FINISHED PER ARCHITECT'S DIRECTION.
- 3. "REMOVAL OF EXISTING" PERTAINS TO ALL EXISTING CONDITIONS, INCLUDING ALL FRAMING, MASONRY, WALL AND CEILING FINISHES, WIRING, CONDUIT PLUMBING, AND ANY CONDITIONS HIDDEN FROM VIEW, ETC. INCLUDING IN CRAWL SPACE.
- 4. REMOVE FINISHES TO VERIFY ASSUMED EXISTING STRUCTURAL FRAMING CONDITIONS TO DETERMINE THAT DEMOLITION WORK WILL NOT AFFECT BUILDING'S STRUCTURAL INTEGRITY.
- 5. NOTIFY ARCHITECT IF EXISTING FRAMING IS DIFFERENT FROM THAT SHOWN ON DRAWINGS. DO NOT PROCEED UNTIL ALTERNATE INSTRUCTIONS HAVE BEEN ISSUED BY ARCHITECT.
- 6. PROVIDE TEMPORARY SHORING AND BRACING WHERE REQUIRED TO MAINTAIN STRUCTURAL INTEGRITY UNTIL PERMANENT STRUCTURE IS COMPLETED.
- 1. MAINTAIN BUILDING IN A WEATHER TIGHT CONDITION UNTIL PERMANENT WEATHERPROOF CLOSURE IS COMPLETED.
- 8. CAREFULLY REMOVE ITEMS TO BE RELOCATED OR REUSED. PROTECT AND STORE ITEMS TO PREVENT DAMAGE UNTIL TIME OF REINSTALLATION.
- 9. DISCONNECT, CAP, AND PLUG MECHANICAL, PLUMBING AND ELECTRICAL SERVICES AT POINTS OF DEMOLITION. LEAVE SERVICES IN A SAFE USABLE CONDITION. ANY PLUMBING, MECHANICAL OR ELECTRICAL SERVICES TO BE ABANDONED ARE TO BE COMPLETELY REMOVED FROM STRUCTURE.
- 10. REMOVE AND/OR RELOCATE EXISTING LIGHT SWITCHES, RECEPTACLES, TELEPHONE AND DATA OUTLETS, THERMOSTATS, AND ANY ACCESSORY AS INDICATED ON THE PLANS. ANY UNIDENTIFIED ITEMS SHALL BE BROUGHT TO THE ARCHITECT'S ATTENTION.
- DISPOSE OF ALL MATERIALS IN STRICT ACCORDANCE WITH ALL APPLICABLE GOVERNMENTAL LAWS, CODES, ORDINANCES, AND REGULATIONS.
- 12. CLEAR AND UNOBSTRUCTED PATHS AND AISLES SHALL BE MAINTAINED AT ALL TIMES THROUGH OCCUPIED SPACES BY THE CONTRACTOR IN STRICT ACCORDANCE WITH ALL APPLICABLE GOVERNMENTAL LAWS, CODES, ORDINANCES, AND REGULATIONS.
- 13. CONTRACTOR SHALL PROTECT ALL AREAS, SURFACES, AND FINISHES NOT TO BE DEMOLISHED. BARRICADES, TEMPORARY DUST PROTECTION, PLASTIC PARTITIONS, ETC. SHALL BE UTILIZED AS REQUIRED TO MAINTAIN SAFE AND CLEAN OCCUPIED AREAS. DEBRIS SHALL BE REMOVED AND WORK AREAS CLEANED AT THE END OF EACH WORK DAY. THIS PORTION IS MANDATORY FOR CONTRACTOR.
- 14. LIFE SAFETY SYSTEMS INCLUDING BUT NOT LIMITED TO EGRESS AND EMERGENCY LIGHTING, SMOKE DETECTORS AND FIRE SPRINKLERS SHALL REMAIN OPERABLE DURING AND AFTER DEMOLITION. CONTRACTOR SHALL NOTIFY LOCAL FIRE AND POLICE DEPARTMENTS, ALARM SERVICE COMPANIES, AND COORDINATE WITH THE OWNER TO SHUT DOWN AND START UP ANY LIFE SAFETY SYSTEM.
- 15. OWNER TO HAVE RIGHT OF FIRST REFUSAL OF ALL EXISTING FIXTURES, FITTINGS, AND ALL OTHER ITEMS BEFORE DISPOSING OF ANY SUCH ITEMS.

### PLAN LEGEND OF DEMOLITION NOTES

- DI (NOT USED)
- REMOVE EXISTING DISHWASHER.
- REMOVE EXISTING SINK. SINK TO BE REPLACED.
- REMOVE EXISTING LAVATORIES. LAVATORIES TO BE REPLACED.
- REMOVE EXISTING TOILETS. TOILETS TO BE REPLACED.
- REMOVE EXISTING URINALS. URINALS TO BE REPLACED.
- REMOVE EXISTING TOILET PARTITION / URINAL SCREEN. TOILET PARTITIONS AND URINAL SCREENS TO BE REPLACED.
- DTA REMOVE EXISTING GRAB BAR. PROVIDE NEW GRAB BAR TO MATCH EXISTING AT EXISTING TOILET ROOM. SEE DRAWING AI-2 FOR NEW TOILET ROOM GRAB BAR LOCATIONS & DETAILS.
- REMOVE EXISTING COUNTERTOP. COUNTERTOP TO BE REPLACED. SEE MILLWORK DRAWING A6-1
- D9 REMOVE EXISTING YCT FLOOR TILES THROUGHOUT, YCT TO BE REPLACED.
- DIØ REMOVE EXISTING CEILING AND LIGHTING FIXTURES THROUGHOUT. CEILING AND LIGHT FIXTURES TO BE REPLACED.
- DII EXISTING CABINETS TO BE REMOVED AND REPLACED WITH NEW CABINETS. SEE DRAWING A6-1.
- DI2 REMOVE EXISTING WINDOW AND SILL. WINDOW AND SILL TO BE REPLACED.
- REMOVE EXISTING DOOR AND FRAME. DOOR AND FRAME TO BE REPLACED. REMOVE EXISTING LOUVER TO REMAIN.
- DIS REMOVE EXISTING CARPET THROUGHOUT. CARPET TO BE REPLACED.



S




3 0

8

REVISED PER ADDENDUM ØØI, DC REVISED PER ADDENDUM ØØI, BJW REVISION SCHEDULE

DC RAWN BY JSB 03-14-2025 AS NOTED



01-08-25 DATE

<u>No.</u>

ISSUED FOR BIDDING

DRAWING ISSUE

- ALL DIMENSIONS TO BE FIELD VERIFIED BEFORE THE START OF CONSTRUCTION. NOTIFY ARCHITECT OF ANY DISCREPANCIES.
- 2. ALL AREAS AFFECTED BY CONSTRUCTION OR DEMOLITION TO BE REPAIRED.
  PATCH, REPAIR, AND RE-FINISH ENTIRE SURFACE OF ALL WALLS, FLOORS, AND
  CEILINGS DISTURBED BY NEW WORK. FINISH TO MATCH EXISTING. ALL NEW
  WORK SHALL BE FINISHED PER ARCHITECT'S DIRECTION.
- 3. "REMOVAL OF EXISTING" PERTAINS TO ALL EXISTING CONDITIONS, INCLUDING ALL FRAMING, MASONRY, WALL AND CEILING FINISHES, WIRING, CONDUIT, PLUMBING, AND ANY CONDITIONS HIDDEN FROM VIEW, ETC. INCLUDING IN CRAWL SPACE.
- 4. REMOVE FINISHES TO VERIFY ASSUMED EXISTING STRUCTURAL FRAMING CONDITIONS TO DETERMINE THAT DEMOLITION WORK WILL NOT AFFECT BUILDING'S STRUCTURAL INTEGRITY.
- 5. NOTIFY ARCHITECT IF EXISTING FRAMING IS DIFFERENT FROM THAT SHOWN ON DRAWINGS. DO NOT PROCEED UNTIL ALTERNATE INSTRUCTIONS HAVE BEEN ISSUED BY ARCHITECT.
- 6. PROVIDE TEMPORARY SHORING AND BRACING WHERE REQUIRED TO MAINTAIN STRUCTURAL INTEGRITY UNTIL PERMANENT STRUCTURE IS COMPLETED.
- 1. MAINTAIN BUILDING IN A WEATHER TIGHT CONDITION UNTIL PERMANENT WEATHERPROOF CLOSURE IS COMPLETED.
- 8. CAREFULLY REMOVE ITEMS TO BE RELOCATED OR REUSED. PROTECT AND STORE ITEMS TO PREVENT DAMAGE UNTIL TIME OF REINSTALLATION.
- 9. DISCONNECT, CAP, AND PLUG MECHANICAL, PLUMBING AND ELECTRICAL SERVICES AT POINTS OF DEMOLITION. LEAVE SERVICES IN A SAFE USABLE CONDITION. ANY PLUMBING, MECHANICAL OR ELECTRICAL SERVICES TO BE ABANDONED ARE TO BE COMPLETELY REMOVED FROM STRUCTURE.
- IØ. REMOVE AND/OR RELOCATE EXISTING LIGHT SWITCHES, RECEPTACLES, TELEPHONE AND DATA OUTLETS, THERMOSTATS, AND ANY ACCESSORY AS INDICATED ON THE PLANS. ANY UNIDENTIFIED ITEMS SHALL BE BROUGHT TO THE ARCHITECT'S ATTENTION.
- 11. DISPOSE OF ALL MATERIALS IN STRICT ACCORDANCE WITH ALL APPLICABLE GOVERNMENTAL LAWS, CODES, ORDINANCES, AND REGULATIONS.
- 12. CLEAR AND UNOBSTRUCTED PATHS AND AISLES SHALL BE MAINTAINED AT ALL TIMES THROUGH OCCUPIED SPACES BY THE CONTRACTOR IN STRICT ACCORDANCE WITH ALL APPLICABLE GOVERNMENTAL LAWS, CODES, ORDINANCES, AND REGULATIONS.
- 13. CONTRACTOR SHALL PROTECT ALL AREAS, SURFACES, AND FINISHES NOT TO BE DEMOLISHED. BARRICADES, TEMPORARY DUST PROTECTION, PLASTIC PARTITIONS, ETC. SHALL BE UTILIZED AS REQUIRED TO MAINTAIN SAFE AND CLEAN OCCUPIED AREAS. DEBRIS SHALL BE REMOVED AND WORK AREAS CLEANED AT THE END OF EACH WORK DAY. THIS PORTION IS MANDATORY FOR CONTRACTOR.
- 14. LIFE SAFETY SYSTEMS INCLUDING BUT NOT LIMITED TO EGRESS AND EMERGENCY LIGHTING, SMOKE DETECTORS AND FIRE SPRINKLERS SHALL REMAIN OPERABLE DURING AND AFTER DEMOLITION. CONTRACTOR SHALL NOTIFY LOCAL FIRE AND POLICE DEPARTMENTS, ALARM SERVICE COMPANIES, AND COORDINATE WITH THE OWNER TO SHUT DOWN AND START UP ANY LIFE SAFETY SYSTEM.
- 15. OWNER TO HAVE RIGHT OF FIRST REFUSAL OF ALL EXISTING FIXTURES, FITTINGS, AND ALL OTHER ITEMS BEFORE DISPOSING OF ANY SUCH ITEMS.

### PLAN LEGEND OF DEMOLITION NOTES

- DI (NOT USED)
- D2 REMOVE EXISTING DISHWASHER
- D3 REMOVE EXISTING SINK, SINK TO BE REPLACED.
- D4 REMOVE EXISTING LAVATORIES. LAVATORIES TO BE REPLACED.

  D5 REMOVE EXISTING TOILETS. TOILETS TO BE REPLACED.
- D6 REMOVE EXISTING URINALS. URINALS TO BE REPLACED.
- DI REMOVE EXISTING TOILET PARTITION / URINAL SCREEN. TOILET PARTITIONS
- AND URINAL SCREENS TO BE REPLACED.


  DIA REMOVE EXISTING GRAB BAR. PROVIDE NEW GRAB BAR TO MATCH EXISTING AT EXISTING TOILET ROOM. SEE DRAWING A1-2 FOR NEW TOILET ROOM GRAB
- BAR LOCATIONS & DETAILS.


  D8 REMOVE EXISTING COUNTERTOP. COUNTERTOP TO BE REPLACED. SEE
- MILLWORK DRAWING A6-1.


  D9 REMOVE EXISTING VCT FLOOR TILES THROUGHOUT, VCT TO BE REPLACED.
- DIØ REMOVE EXISTING CEILING AND LIGHTING FIXTURES THROUGHOUT. CEILING AND LIGHT FIXTURES TO BE REPLACED.
- DII EXISTING CABINETS TO BE REMOVED AND REPLACED WITH NEW CABINETS. SEE DRAWING A6-1.
- DI2 REMOVE EXISTING WINDOW AND SILL. WINDOW AND SILL TO BE REPLACED.


  DI3 REMOVE EXISTING DOOR AND FRAME. DOOR AND FRAME TO BE REPLACED.
- DI4 REMOVE EXISTING LOUVER TO REMAIN.
- DIS REMOVE EXISTING LOUVER TO REITIAIN.

  DIS REMOVE EXISTING CARPET THROUGHOUT. CARPET TO BE REPLACED.
















TO ELECTRICAL, MECHANICAL, AND FIRE PROTECTION DRAWINGS FOR INSTALLATION INFORMATION THAT SUPERCEDES ARCHITECTURAL DRAWINGS.





**a** 

REVISED PER ADDENDUM ØØI, BJW | 2-26-2025 REVISION SCHEDULE


DC DRAWN BY: JSB *Ø*3-14-2*Ø*25 AS NOTED


2199.01 JOB NO.


BASEMENT REFLECTED CEILING PLAN SCALE: 1/4" = 1'-0"


ISSUED FOR BUILDING PERMITS Ø4-1Ø-25 Ø1-Ø8-25 ISSUED FOR BIDDING DATE DRAWING ISSUE <u>No.</u>

SHOWN IS TO BE FIELD VERIFIED.









VINELAND SENIOR CENTER
103 8 6TH STREET
VINELAND, NEW JERSEY 08360

STARTING CONSTRUCTION

STARTING CONSTRUCTION

CEPALD & BLACKMAN ID

	00		<b>)</b>
ERVED			
S RES			
ALL RIGHTS RESERVED	H		
	NO.	DESCRIPTION	DATE
NERS, P.A.		REVISION SCHEDU	ILE

8 8	DRAWN BY:	DC
DESIGN	CHECKED BY:	JSB
OSK	DATE:	03-14-2025
	SCALE:	AS NOTED
<u>ن</u>		

2199.01

JOB NO.

Ø4-1Ø-25

Ø1-Ø8-25

DATE

ISSUED FOR BUILDING PERMITS

DRAWING ISSUE

ISSUED FOR BIDDING



o Z

	CONTRACTOR SHALL CHE	FIELD CONDITIONS PRICE STARTING CONSTRUC	GERALD S. BLACKMA
L RIGHIS RESERVED			
-L RIGHIS	<u></u>	CONFORMANCE REVISIONS, DC	4-10-2025

	CONTRACT	START	GERALC NJ 1
٥			
RESERVED			
ALL RIGHTS RI			
	3	CONFORMANCE REVISIONS, DC	4-10-2025
	NO.	DESCRIPTION	DATE
ERS, P.A.		REVISION SCHEDU	JLE

3	CONFORMANCE REVISIONS, DC	4-10-2025
NO.	DESCRIPTION	DATE
	REVISION SCHEDU	JLE
	REVISION SCHEDU	JLE

NO.	DESCRIP'	TION	DATE
	REVISION	SCHEDU	JLE
DR	RAWN BY:	DC	
CH	IECKED BY:	JSB	
DA	TE:	Ø3-14·	-2Ø25
SC	CALE:	AS N	OTE

<u>N</u>	DRAWN BY:	DC
DESIGN	CHECKED BY:	JSB
OSK	DATE:	<i>Ø</i> 3-14-2 <i>Ø</i> 25
Ш	SCALE:	AS NOTED
0		
<u></u>	JOB NO.	2199.01
一 六		·

Ø4-1Ø-25

Ø1-Ø8-25

DATE


<u>No.</u>


ISSUED FOR BUILDING PERMITS

DRAWING ISSUE

ISSUED FOR BIDDING







OR CENTER OVENENTS IREET RSEY 08360

NELAND SENIOR CANTERIOR SENIOR CANTERIOR INTERPRETATION SENTERSET SINELAND, NEW JERSEY 6

KITLE

GERALD S. BLACKMAN JR.
NJ LICENSE # 17113

STARTING CONDITION OF STARTING CONDITION OF


10.	DESCRIPTION		DAT
	REVISION	SCHEDU	JLE
DR	AWN BY:	DC/B	JW
СН	IECKED BY:	JSB	
DΑ	TE:	Ø1-Ø8-	2Ø25
SC	ALE:	AS NO1	ED

JOB NO. 2199.01

DATE

<u>No.</u>

DRAWING ISSUE



PROJECT

VINELAND SENIOR CEN

EXTERIOR MPROVEME

100 8 6 TH STREET

VINELAND, NEW JERSEY 6834

Mo

SIGN TS & I

GERALD S. BLACKMAN JR.

NO. DESCRIPTION DATE

REVISION SCHEDULE

DRAWN BY: DC / BJW
CHECKED BY: JSB
DATE: Ø1-Ø8-2Ø25
SCALE: AS NOTED

JOB NO. 2199.01

NOTE: ALL CONDITIONS AND REPRESENTATIONS
ON THIS DRAWING ARE APPROXIMATE RENDITIONS
OF ACTUAL CONDITIONS ALL INFORMATION
SHOWN IS TO BE FIELD VERIFIED.


DRAWING ISSUE

ISSUED FOR BIDDING

01-08-2025

DATE

<u>No.</u>



 $\mathbf{M}$ 

a

DESCRIPTION

REVISION	SCHEDULE
RAWN BY:	DC/BJW
HECKED BY:	JSB
ATE:	Ø1-Ø8-2Ø25
CALE:	AS NOTED

2199.01 OB NO.

NOTE: ALL CONDITIONS AND REPRESENTATIONS ON THIS DRAWING ARE APPROXIMATE RENDITIONS

ØI-Ø8-2Ø25

DATE


<u>No.</u>


OF ACTUAL CONDITIONS ALL INFORMATION


SHOWN IS TO BE FIELD VERIFIED.


DRAWING ISSUE


ISSUED FOR BIDDING


















NOTE: ALL CONDITIONS AND REPRESENTATIONS ON THIS DRAWING ARE APPROXIMATE RENDITIONS OF ACTUAL CONDITIONS ALL INFORMATION SHOWN IS TO BE FIELD VERIFIED.

ISSUED FOR BUILDING PERMITS	2	Ø4-1Ø-25
ISSUED FOR BIDDING	1	Ø1-Ø8-25
DRAWING ISSUE	<u>No.</u>	DATE



9

DC

2199.01

JOB NO.

*Ø*3-14-2*Ø*25 AS NOTED

JSB